

## **EXHIBIT “A”**

### **CONDITIONS OF APPROVAL**

**Planning Application No.:** **PLN23-0146 Tentative Tract Map No. 38766 and Plot Plan No. PLN23-0147 “Garbani and Evans**

**Project Description:** **Tentative Tract Map No. 37866 (PLN23-0146) and Plot Plan No. PLN23-0147** proposes a subdivision of an 18.25-acre property into 67 single-family lots located at the northwest corner of Garbani Road and Evans Road pursuant to Senate Bill (SB) 330 - Housing Crisis Act of 2019. Each lot will contain a main dwelling and an architecturally compatible detached accessory dwelling unit (ADU) for a total of 134 units. The main access to the site will be from Evans Road with an emergency only access point on Garbani Road. Project amenities will include a linear park along Evans Road, dog park, and recreation center with pool, BBQ's, picnic tables, event room with kitchen, bathrooms and showers.

**Assessor's Parcel No.:** 360-180-021

**MSHCP Category:** Residential density less than 8 du/acre

**DIF Category:** Single-Family Residential (use fees effective July 17, 2023 until SB 330 Expiration Date noted below)

**TUMF Category:** Determined by Western Riverside Council of Governments (WRCOG)

**Quimby Category:** Single-Family Residential

**Approval Date:** October 9, 2024

**Expiration Date:** October 9, 2027

**SB330 Expiration Date:** April 9, 2027

### **Within 48 Hours of the Approval of This Project**

- 1 **Indemnification.** Within 48 hours of project approval, the Applicant/developer shall indemnify, defend, and hold harmless the City of Menifee and its elected city council, appointed boards, commissions, committees, officials, employees, volunteers, contractors, consultants, and agents from and against any and all claims, liabilities, losses, fines, penalties, and expenses, including without limitation litigation expenses and attorney's fees, arising out of either the City's approval of the Project or actions related to the Property or the acts, omissions, or operations of the applicant/developer and its directors, officers, members, partners, employees, agents, contractors, and subcontractors of each person or entity comprising the applicant/developer with respect to the ownership, planning, design, construction, and maintenance of the Project and the Property for which the Project is being approved.
- 2 **Filing Notice of Determination or Exemption.** Within 48 hours of project approval, the Planning Division will determine the appropriate fees for the Notice of Determination (NOD) filing and request the payment of fees to the City of Menifee in the form of a check or cash. Upon receipt of payment, the Planning Division will file the NOD with the relevant agencies as required under Public Resources Code, California Code of Regulations and California Fish and Game Code.

**Section I: Community Development Department**

**Section II: Engineering/Public Works Department**

**Section III: Building and Safety Department**

**Section IV: Riverside County Fire Department**

**Section V: Other Agency/Departments**

**Section I:**

**Community Development**  
**Department**

## **GENERAL CONDITIONS**

1. **Senate Bill SB330.** Tentative Tract Map 38766 Garbani and Evans (TR38766) is subject to the requirements of Senate Bill 330 Housing Crisis Act of 2019 (SB330). This bill freezes Development Impact and User Fees to those in effect at the time the SB330 application was deemed submitted unless otherwise noted in SB330. The date the SB330 Pre-application was submitted is July 17, 2023. Per SB330, if construction has not commenced within 2.5 years of the date of Entitlement Approval or otherwise noted in SB330, this condition becomes null and void. As of the date this condition becomes null and void (April 9, 2027), all current City of Menifee fees are applicable to this project. Government Code section 65589.5, subdivision (o).
2. **Exhibits.** The project shall be constructed as approved, and as shown in the attachments to the accompanying staff report. The project shall be in compliance with City of Menifee Municipal Code. Any subsequent changes shall be processed per Menifee Municipal Code Section 9.30.120 Modifications to Previously Approved Permits.
3. **Mitigation Monitoring.** The applicant shall comply with, prepare and submit a written report to the Community Development Director demonstrating compliance with those conditions of approval and mitigation measures of this tract map which must be satisfied prior to the issuance of a grading permit for review and approval. The Community Development Director may require inspection or other monitoring to ensure such compliance.
4. **Ninety (90) Days.** The applicant has ninety (90) days from the date of approval of these conditions to protest the imposition of any and all fees, dedications, reservations and/or other exactions imposed on this project as a result of this approval or conditional approval of this project per Government Code Section 66020.
5. **Subsequent Submittals.** Any subsequent submittals required by these Conditions of Approval, including but not limited to grading plan, building plan or mitigation monitoring review and appropriate fees paid as may be in effect at the time of submittal, as required by Resolution No. 24-1423 (Cost of Services Fee Study), or any successor thereto. Each submittal shall be accompanied with a letter clearly indicating which condition or conditions the submittal is intended to comply with.
  - a) This project is subject to SB330 as noted in Condition No. 1 above. Use fees effective July 17, 2023 until SB330 Expiration Date of March 25, 2027. After March 25, 2027, the current user fees in place shall be effective.

6. **Expiration Date.** This approval shall become null and void three (3) years from the date of approval, unless the appropriate permits have been obtained and construction, defined as permit obtainment, commencement of construction of the primary building on site, and successful completion of the first Building and Safety Division inspection or an extension of time application has been submitted to the Planning Division prior to the expiration date. Extensions may be granted per Menifee Municipal Code.
7. **Modifications or Revisions.** The applicant shall obtain City approval for any modifications or revisions to the approval of this project.
8. **Comply with Ordinances.** This project shall comply with the standards of the City of Menifee Development Code, City of Menifee Municipal Code, City of Menifee Design Guidelines and all other applicable ordinances and State and Federal codes and regulations.
9. **Outside Lighting.** Any outside lighting shall be hooded and directed so as not to shine directly upon adjoining property or public rights-of-way and so as to prevent either the spillage of lumens or reflection into the sky.
10. **Map Act Compliance.** This land division shall comply with the State of California Subdivision Map Act and to all requirements of Title 7 of the City of Menifee Municipal Code, unless modified by the conditions listed herein.
11. **No Offsite Subdivision Signage.** No offsite subdivision signs advertising this land division/development are permitted, other than those allowed under the Menifee Municipal Code. Violation of this condition of approval may result in no further permits of any type being issued for this subdivision until the unpermitted signage is removed.
12. **Development Fees.** The applicant shall pay all applicable development impact fees including but not limited to Development Impact [prior to building occupancy], Multi-Species Habitat Conservation Plan (MSHCP) [prior to building permit issuance], Quimby [prior to building occupancy], Stephen's Kangaroo Rat (KRAT) [prior to grading permit issuance], and School Fees [prior to building permit issuance].
13. **Phases.** Construction of this project may be done progressively in phases provided a phasing plan is submitted with appropriate fees to the Planning Division and approved prior to issuance of any Building Permits.
14. **Property Maintenance.** All parkways, entryway medians, on-site and off-site landscaping, walls, fencing, recreational facilities, basins, and on-site lighting shall be maintained by the property owner or private entity or the City of Menifee Community Facilities District (CFD).

All landscaping and similar improvements not properly maintained by a

property owners association, property owner or the common area maintenance director must be annexed into a Lighting and Landscape District, or other mechanism as determined by the City of Menifee.

The land divider, or any successor-in-interest to the land divider, shall be responsible for maintenance and upkeep of all slopes, landscaped areas and irrigation systems within the land division until such time as those operations are the responsibility of a property owner's association, or any other successor-in-interest.

The owners of each individual lot shall be responsible for maintaining all landscaping between the curb of the street and the proposed sidewalk and side yard landscaping between the curb of the street and proposed fencing, unless the landscaping is included within a separate common lot maintained by an HOA or other entity acceptable to the City of Menifee.

15. **Landscape Plans.** All landscaping plans shall be prepared in accordance with the City's Water Efficient Landscape Ordinance. Such plans shall be reviewed and approved by the Community Development Department, and the appropriate maintenance authority.
16. **Human Remains.** If human remains are encountered, State Health and Safety Code Section 7050.5 states that no further disturbance shall occur until the Riverside County Coroner has made the necessary findings as to origin. Further, pursuant to Public Resource Code Section 5097.98(b) remains shall be left in place and free from disturbance until a final decision as to the treatment and disposition has been made. If the Riverside County Coroner determines the remains to be Native American, the Native American Heritage Commission shall be contacted within the period specified by law (24 hours). Subsequently, the Native American Heritage Commission shall identify the "most likely descendant." The most likely descendant shall then make recommendations and engage in consultation concerning the treatment of the remains as provided in Public Resources Code Section 5097.98.
17. **Non-Disclosure of Location Reburials.** It is understood by all parties that unless otherwise required by law, the site of any reburial of Native American human remains or associated grave goods shall not be disclosed and shall not be governed by public disclosure requirements of the California Public Records Act. The Coroner, parties, and Lead Agencies, will be asked to withhold public disclosure information related to such reburial, pursuant to the specific exemption set forth in California Government Code 6254 (r).
18. **Inadvertent Archeological Find.** If during ground disturbance activities, unique cultural resources are discovered that were not assessed by the archaeological report(s) and/or environmental assessment conducted prior

to project approval, the following procedures shall be followed. Unique cultural resources are defined, for this condition only, as being multiple artifacts in close association with each other, but may include fewer artifacts if the area of the find is determined to be of significance due to its sacred or cultural importance as determined in consultation with the Native American Tribe(s).

- a) All ground disturbance activities within 100 feet of the discovered cultural resources shall be halted until a meeting is convened between the developer, the archaeologist, the tribal representative(s) and the Community Development Director to discuss the significance of the find.
- b) At the meeting, the significance of the discoveries shall be discussed and after consultation with the tribal representative(s) and the archaeologist, a decision shall be made, with the concurrence of the Community Development Director, as to the appropriate mitigation (documentation, recovery, avoidance, etc.) for the cultural resources.
- c) Grading of further ground disturbance shall not resume within the area of the discovery until an agreement has been reached by all parties as to the appropriate mitigation. Work shall be allowed to continue outside of the buffer area and will be monitored by additional Tribal monitors if needed.
- d) Treatment and avoidance of the newly discovered resources shall be consistent with the Cultural Resources Management Plan and Monitoring Agreements entered into with the appropriate tribes. This may include avoidance of the cultural resources through project design, in-place preservation of cultural resources located in native soils and/or re-burial on the Project property so they are not subject to further disturbance in perpetuity as identified in Non-Disclosure of Reburial Condition.
- e) Pursuant to Calif. Pub. Res. Code § 21083.2(b) avoidance is the preferred method of preservation for archaeological resources and cultural resources. If the landowner and the Tribe(s) cannot agree on the significance or the mitigation for the archaeological or cultural resources, these issues will be presented to the City Community Development Director for decision. The City Community Development Director shall make the determination based on the provisions of the California Environmental Quality Act with respect to archaeological resources, recommendations of the project archeologist and shall take into account the cultural and religious principles and practices of the Tribe. Notwithstanding any other rights available under the law, the decision of the City Community Development Director shall be appealable to the City Planning Commission and/or City Council."

19. **Cultural Resources Disposition.** In the event that Native American cultural resources are discovered during the course of ground disturbing



activities (inadvertent discoveries), the following procedures shall be carried out for final disposition of the discoveries:

a. One or more of the following treatments, in order of preference, shall be employed with the tribes. Evidence of such shall be provided to the City of Menifee Planning Division:

i. Preservation-In-Place of the cultural resources, if feasible. Preservation in place means avoiding the resources, leaving them in the place where they were found with no development affecting the integrity of the resources.

ii. Reburial of the resources on the Project property. The measures for reburial shall include, at least, the following: Measures and provisions to protect the future reburial area from any future impacts in perpetuity. Reburial shall not occur until all legally required cataloging and basic recordation have been completed, with an exception that sacred items, burial goods and Native American human remains are excluded. Any reburial process shall be culturally appropriate. Listing of contents and location of the reburial shall be included in the confidential Phase IV report. The Phase IV Report shall be filed with the City under a confidential cover and not subject to Public Records Request.

iii. If preservation in place or reburial is not feasible then the resources shall be curated in a culturally appropriate manner at a Riverside County curation facility that meets State Resources Department Office of Historic Preservation Guidelines for the Curation of Archaeological Resources ensuring access and use pursuant to the Guidelines. The collection and associated records shall be transferred, including title, and are to be accompanied by payment of the fees necessary for permanent curation. Evidence of curation in the form of a letter from the curation facility stating that subject archaeological materials have been received and that all fees have been paid, shall be provided by the landowner to the City. There shall be no destructive or invasive testing on sacred items, items of Native American Cultural Patrimony, burial goods and Native American human remains. Results concerning findings of any inadvertent discoveries shall be included in the Phase IV monitoring report.

20. **Inadvertent Paleontological Find.** In the event that fossils or fossil-bearing deposits are discovered during construction, excavations within fifty (50) feet of the find shall be temporarily halted or diverted. The contractor shall notify a qualified paleontologist to examine the discovery. The paleontologist shall document the discovery as needed in accordance with Society of Vertebrate Paleontology standards, evaluate the potential resource, and assess the significance of the find under the criteria set forth in CEQA Guidelines Section 15064.5. The paleontologist shall notify the Planning Division to determine procedures that would be followed before construction is allowed to resume at the location of the find. If in consultation with the paleontologist, the Project proponent determines that avoidance is not feasible, the paleontologist shall prepare an excavation plan for mitigating the effect of the Project on the qualities that make the

resource important. The plan shall be submitted to the Planning Division for review and approval and the Project proponent shall implement the approval plan.

#### **PRIOR TO FINAL MAP**

21. **Processing Fees.** Prior to final map recordation, the Planning Division shall determine if any fees for the project are in a negative balance. If so, any outstanding fees shall be paid by the applicant.
22. **Final Map Required.** After the approval of the TENTATIVE MAP and prior to the expiration of said map, the land divider shall cause the real property included within the TENTATIVE MAP, or any part thereof, to be surveyed and a FINAL MAP thereof prepared in accordance with the current Engineering Department - Survey Division requirements, the conditionally approved TENTATIVE MAP, and in accordance with City of Menifee Municipal Code.
23. **ECS.** The land divider shall prepare an Environmental Constraints Sheet (ECS) in accordance with Menifee Municipal Code, which shall be submitted as part of the plan check review of the FINAL MAP. A note shall be placed on the FINAL MAP "Environmental Constraint Sheet affecting this map is on file at the City of Menifee Public Works and Engineering Department, in E.C.S Book \_\_\_, Page \_\_\_."
24. **ECS Note on Dark Sky Lighting.** The following Environmental Constraints Note shall be placed on the ECS: "This property is subject to lighting restrictions as required by Menifee Municipal Code Chapter 6 (Ordinance No. 2009-024), which are intended to reduce the effects of night lighting on the Mount Palomar Observatory. All proposed outdoor lighting systems shall be in conformance with Menifee Municipal Code Chapter 6."

#### **PRIOR TO GRADING PERMIT ISSUANCE**

25. **Processing Fees.** Prior to issuance of grading permits, the Planning Division shall determine if any fees for the project are in a negative balance. If so, any outstanding fees shall be paid by the applicant.
26. **Stephen's Kangaroo Rat Fee.** The applicant shall pay the appropriate Stephen's Kangaroo Rat Fee prior to grading permit issuance.
27. **Mitigation Monitoring.** Prior to issuance of grading permits, the applicant shall prepare and submit a written report to the Community Development Director for review and approval demonstrating compliance with the standard conditions of approval and mitigation measures identified in the CEQA Guidelines § 15183 Compliance Environmental Checklist for this project which must be satisfied. The Community Development Director may require inspection or other monitoring to ensure such compliance.

28. **Fugitive Dust Control.** The permittee shall implement fugitive dust control measures in accordance with Southern California Air Quality Management District (SCAQMD) Rule 403. The permittee shall include in construction contracts the control measures required under Rule 403 at the time of development, including the following:
- a. Use watering to control dust generation during demolition of structures or break-up of pavement. The construction area and vicinity (500-foot radius) must be swept (preferably with water sweepers) and watered at least twice daily. Site wetting must occur often enough to maintain a ten (10) percent surface soil moisture content throughout all earth moving activities. All unpaved demolition and construction areas shall be wetted at least twice daily during excavation and construction, and temporary dust covers shall be used to reduce dust emissions and meet SCAQMD District Rule 403. Wetting could reduce fugitive dust by as much as fifty percent (50%).
  - b. Water active grading/excavation sites and unpaved surfaces at least three (3) times daily;
  - c. All paved roads, parking and staging areas must be watered at least once every two (2) hours of active operations;
  - d. Site access points must be swept/washed within thirty (30) minutes of visible dirt deposition;
  - e. Sweep daily (with water sweepers) all paved parking areas and staging areas;
  - f. Onsite stockpiles of debris, dirt or rusty material must be covered or watered at least twice daily;
  - g. Cover stockpiles with tarps or apply non-toxic chemical soil binders;
  - h. All haul trucks hauling soil, sand and other loose materials must either be covered or maintain two feet of freeboard;
  - i. All inactive disturbed surface areas must be watered on a daily basis when there is evidence of wind drive fugitive dust;
  - j. Install wind breaks at the windward sides of construction areas;

- k. Operations on any unpaved surfaces must be suspended when winds exceed twenty-five (25) mph;
- l. Suspend excavation and grading activity when winds (instantaneous gusts) exceed fifteen (15) miles per hour over a thirty (30) minute period or more, so as to prevent excessive amounts of dust;
- m. All haul trucks must have a capacity of no less than twelve and three-quarter (12.75) cubic yards;
- n. All loads shall be secured by trimming, watering or other appropriate means to prevent spillage and dust;
- o. Traffic speeds on unpaved roads must be limited to fifteen (15) miles per hour;
- p. Provide daily clean-up of mud and dirt carried onto paved streets from the site;
- q. Install wheel washers for all exiting trucks, or wash off the tires or tracks of all trucks and equipment leaving the site;
- r. All materials transported off-site shall be either sufficiently watered or securely covered to prevent excessive amount of dust;
- s. Operations on any unpaved surfaces must be suspended during first and second stage smog alerts; and,
- t. An information sign shall be posted at the entrance to each construction site that identifies the permitted construction hours and provides a telephone number to call and receive information about the construction project or to report complaints regarding excessive fugitive dust generation. Any reasonable complaints shall be rectified within twenty-four (24) hours of their receipt.

29. **Archeologist Retained.** Prior to issuance of a grading permit the project applicant shall retain a Riverside County qualified archaeologist to monitor all ground disturbing activities in an effort to identify any unknown archaeological resources.

- a. The Project Archaeologist and the Tribal monitor(s) shall manage and oversee monitoring for all initial ground disturbing activities and excavation of each portion of the project site including clearing, grubbing, tree removals, mass or rough grading, trenching, stockpiling of materials, rock crushing, structure demolition and etc. The Project Archaeologist and the Tribal

monitor(s), shall have the authority to temporarily divert, redirect or halt the ground disturbance activities to allow identification, evaluation, and potential recovery of cultural resources in coordination with any required special interest or tribal monitors.

- b. The developer/permit holder shall submit a fully executed copy of the contract to the Planning Division to ensure compliance with this condition of approval. Upon verification, the Planning Division shall clear this condition.
- c. In addition, the Project Archaeologist, in consultation with the Consulting Tribe(s), the contractor, and the City, shall develop a Cultural Resources Management Plan (CRMP) in consultation pursuant to the definition in AB52 to address the details, timing and responsibility of all archaeological and cultural activities that will occur on the project site. A consulting tribe is defined as a tribe that initiated the AB 52 tribal consultation process for the Project, has not opted out of the AB52 consultation process, and has completed AB 52 consultation with the City as provided for in Cal Pub Res Code Section 21080.3.2(b)(1) of AB52. Details in the Plan shall include:
  - d. Project grading and development scheduling;
    - i. The Project archeologist and the Consulting Tribes(s) shall attend the pre-grading meeting with the City, the construction manager and any contractors and will conduct a mandatory Cultural Resources Worker Sensitivity Training to those in attendance. The Training will include a brief review of the cultural sensitivity of the Project and the surrounding area; what resources could potentially be identified during earthmoving activities; the requirements of the monitoring program; the protocols that apply in the event inadvertent discoveries of cultural resources are identified, including who to contact and appropriate avoidance measures until the find(s) can be properly evaluated; and any other appropriate protocols. All new construction personnel that will conduct earthwork or grading activities that begin work on the Project following the initial Training must take the Cultural Sensitivity Training prior to beginning work and the Project archaeologist and Consulting Tribe(s) shall make themselves available to provide the training on an as-needed basis.
    - ii. The protocols and stipulations that the contractor, City, Consulting Tribe(s) and Project archaeologist will follow in

the event of inadvertent cultural resources discoveries, including any newly discovered cultural resource deposits that shall be subject to a cultural resource's evaluation.

30. **Native American Monitoring (Pechanga/Soboba).** Tribal monitor(s) shall be required on-site during all ground-disturbing activities, including grading, stockpiling of materials, engineered fill, rock crushing, etc. The land divider/permit holder shall retain a qualified tribal monitor(s) from the Pechanga Band of Luiseno Indians and Soboba Band of Luiseno Indians. Prior to issuance of a grading permit, the developer shall submit a copy of a signed contract between the above-mentioned Tribe and the land divider/permit holder for the monitoring of the project to the Planning Division and to the Engineering Department. The Tribal Monitor(s) shall have the authority to temporarily divert, redirect or halt the ground-disturbance activities to allow recovery of cultural resources, in coordination with the Project Archaeologist.
31. **Paleontologist Required.** This site is mapped as having a high potential for paleontological resources (fossils) at shallow depth. Therefore, PRIOR TO ISSUANCE OF GRADING PERMITS:
  - a. The applicant shall retain a qualified paleontologist approved by the City of Menifee to create and implement a project-specific plan for monitoring site grading/earthmoving activities which exceeds 5 feet in depth in native sedimentary.
  - b. The project paleontologist retained shall review the approved Tentative Tract Map and shall conduct any pre-construction work necessary to render appropriate monitoring and mitigation requirements as appropriate. These requirements shall be documented by the project paleontologist in a Paleontological Resource Impact Mitigation Program (PRIMP). This PRIMP shall be submitted to the Planning Division for review and approval prior to issuance of a Grading Permit.
  - c. Information to be contained in the PRIMP, at a minimum and in addition to other industry standard and Society of Vertebrate Paleontology standards, are as follows:
    - i. The project paleontologist shall participate in a pre-construction project meeting with development staff and construction operations to ensure an understanding of any mitigation measures required during construction, as applicable.
    - ii. Paleontological monitoring of earthmoving activities will be conducted on an as-needed basis by the project

paleontologist during all earthmoving activities that may expose sensitive strata. Earthmoving activities in areas of the project area where previously undisturbed strata will be buried but not otherwise disturbed will not be monitored. The project paleontologist or his/her assign will have the authority to reduce monitoring once he/she determines the probability of encountering fossils has dropped below an acceptable level.

- iii. If the project paleontologist finds fossil remains, earthmoving activities will be diverted temporarily around the fossil site until the remains have been evaluated and recovered. Earthmoving will be allowed to proceed through the site when the project paleontologist determines the fossils have been recovered and/or the site mitigated to the extent necessary.
- iv. If fossil remains are encountered by earthmoving activities when the project paleontologist is not onsite, these activities will be diverted around the fossil site and the project paleontologist called to the site immediately to recover the remains.
- v. If fossil remains are encountered, fossiliferous rock will be recovered from the fossil site and processed to allow for the recovery of smaller fossil remains. Test samples may be recovered from other sampling sites in the rock unit if appropriate.
- vi. Any recovered fossil remains will be prepared to the point of identification and identified to the lowest taxonomic level possible by knowledgeable paleontologists. The remains then will be curated (assigned and labeled with museum\* repository fossil specimen numbers and corresponding fossil site numbers, as appropriate; places in specimen trays and, if necessary, vials with completed specimen data cards) and catalogued, an associated specimen data and corresponding geologic and geographic site data will be archived (specimen and site numbers and corresponding data entered into appropriate museum repository catalogs and computerized data bases) at the museum repository by a laboratory technician. The remains will then be accessioned into the museum\* repository fossil collection, where they will be permanently stored, maintained, and, along with associated specimen and site data, made available for future study by qualified scientific investigators.

- vii. The City of Menifee must be consulted on the repository/museum to receive the fossil material prior to being curated.
  - viii. A qualified paleontologist shall prepare a report of findings made during all site grading activity with an appended itemized list of fossil specimens recovered during grading (if any). This report shall be submitted to the Planning Division for review and approval prior to building final inspection as described elsewhere in these conditions.
  - ix. All reports shall be signed by the project paleontologist and all other professionals responsible for the report's content (e.g. Professional Geologist, Professional Engineer, etc.), as appropriate. Two wet-signed original copies of the report shall be submitted directly to the Planning Division along with a copy of this condition, deposit-based fee and the grading plan for appropriate case processing and tracking.
- 32. **Pre-Grading Meeting.** The qualified archaeologist shall attend the pre-grading meeting with the contractors to explain and coordinate the requirements of the monitoring program, including a cultural sensitivity training component.
- 33. **Burrowing Owl Pre-Construction Survey.** The Project Developer shall retain a qualified biologist to conduct a pre-construction survey for Burrowing Owl within 30 days prior to the start of construction. The results of the single one-day survey would be submitted to the City prior to obtaining a grading permit. If Burrowing Owl are not detected during the pre-construction survey, no further mitigation is required. If Burrowing Owl are detected during the pre-construction survey, the Project applicant and a qualified consulting biologist will be required to prepare and submit for approval a Burrowing Owl relocation program.
- 34. **Nesting Bird Pre-Construction Survey.** Prior to vegetation clearance, the Project applicant shall retain a qualified biologist to conduct a pre-construction nesting bird survey in accordance with the following:
  - a. The final walkover survey shall be conducted no more than three (3) days prior to the initiation of clearance/construction work;
  - b. If pre-construction surveys indicate that bird nests are not present or are inactive, or if potential habitat is unoccupied, no further mitigation is required;
  - c. If active nesting birds are found during the surveys, a species-specific no-disturbance buffer zone shall be established by a



qualified biologist around active nests until a qualified biologist determines that all young have fledged (i.e., no longer reliant upon the nest).

- d. It is recommended that close coordination between the developer of the site, the City of Menifee, the project engineer, and the consulting qualified biologist to consider vegetation clearance outside of the normal bird nesting season (usually February 1 – August 31) to avoid impacts to nesting birds which would potentially violate the federal Migratory Bird Treaty Act. It should be noted that bird nesting season is increasingly less-definitive for some year-round resident species such as hummingbirds and raptors. Further, ground-dwelling birds such as burrowing owls, can be affected nearly any time of the year if present. It is therefore advisable to conduct a preconstruction bird survey no matter the time of year.
- e. Removal of vegetation necessitates installation of appropriate Storm Water Pollution Prevention Plan “SWPPP” measures, particularly if development subsequent to grading is not undertaken immediately, therefore careful timing of the project schedule and implementation measures is necessary to avoid water quality impacts.

#### **PRIOR TO BUILDING PERMIT ISSUANCE**

- 35. **Processing Fees.** Prior to issuance of building permits, the Planning Division shall determine if any fees for the project are in a negative balance. If so, any outstanding fees shall be paid by the applicant.
- 36. **Development Fees.** The applicant shall pay the following:
  - Multi-Species Habitat Conservation Plan Fees (MSHCP) shall be paid prior to issuance of each residential unit within the project.
  - School fees shall be paid to the Perris Union High School District and the Menifee Union School District. Provide proof of payment (receipts) to the Planning Department prior to building permit issuance of each residential unit.
  - Quimby fee amounts (parks and recreation fee) shall be determined in coordination with the Community Services Department prior to issuance of the first residential unit within the project. Payment of Quimby fees must be completed prior to issuance of building occupancy of each unit.
- 37. **Dark Sky Ordinance.** All streetlights and other outdoor lighting shall be shown on electrical plans submitted to the Building and Safety Division and the Planning Division for plan check approval and shall comply with the requirements of Menifee Municipal Code Chapter 6.01, the “Dark Sky Ordinance”, and the General Plan.

38. **Roof Mounted Equipment.** Roof-mounted mechanical equipment shall not be permitted within the subdivision, however, solar equipment or any other energy-saving devices shall be permitted with Planning Division approval.
39. **Utilities Underground.** All utilities, except electrical lines rated 33 kV or greater, shall be installed underground. If the applicant provides to the Building and Safety Division and the Planning Division a definitive statement from the utility provider refusing to allow underground installation of the utilities they provide, this condition shall be null and void with respect to that utility.
40. **Minor Plot Plans.** Prior to building permit issuance, the applicant shall submit the following minor plot plan applications to the Planning Division (pursuant to Menifee Municipal Code) for review and approval. The fee for each submittal will be determined by Resolution No. 24-1423 Cost of Services Fee Study and Planning Division Fee Schedule at the time of application submittal. Minor Plot Plan Submittals include:
- a. Model Home Complex (MHC) – Plotting, landscaping and irrigation for the model home complex. Performance Securities will be required prior to approval of this minor plot plan.
  - b. On-Site Landscaping – all HOA or private entity maintained landscaping and irrigation. Performance Securities will be required prior to approval of this minor plot plan.
  - c. Front Yard Typicals (FYT's) – all homeowner-maintained landscaping in front yards (if applicable).
  - d. Private Slopes – all homeowner-maintained landscaping on downslopes within a property (if applicable).

Additional submittal requirements can be found in the minor plot plan submittal checklist found on the Community Development Department's website. All minor plot plans must be approved prior to the issuance of any production lot within the tract.

This project is subject to SB330 as noted in Condition No. 1 above. Use fees effective July 17, 2023 until SB330 Expiration Date of April 9, 2027. After April 9, 2027, the current user fees in place shall be effective.

41. **Performance Securities.** Performance securities, in amounts to be determined by the Director of Community Development to guarantee the installation of plantings, irrigation system, walls and/or fences, in accordance with the approved plan, shall be filed with the Department of

Community Development. Securities may require review by City Attorney and other staff. Permit holder is encouraged to allow adequate time to ensure that securities are in place. The performance security may be released one year after structural final, inspection report, and the One-Year Post Establishment report confirms that the planting and irrigation components have been adequately installed and maintained. A cash security shall be required when the estimated cost is \$2,500.00 or less. At applicant's election, a cash security may also be used for amounts exceeding \$2,500.

42. **Landscape Inspections.** Prior to issuance of Building Permits, the permit holder shall open a Landscape Deposit Based Fee case and deposit the prevailing deposit amount to cover the pre-inspection, initial installation inspection, Six (6) Month and One Year Landscape Inspections.
43. **Landscape and Amenity Timing.** Prior to occupancy of 25% of residential units within the tract, the following shall be installed and open to the residents:
  - a) The dog park, paseo and recreation center shall be complete and open to the public. The Community Development Director shall have the ability to defer the installation of landscaping and central amenities but may require performance securities and additional deposits to cover administrative costs. Under no circumstance shall landscaping or central amenities be deferred if 50% of the units have been issued occupancy or final.
  - a) Any landscape or open space lot shall be completed with the occupancy of any adjacent residential lot/unit. This does not include the dog park, paseo or recreation center

In the event the rental community proposal does not move forward and individual tract lots are sold to different property owners, the following shall apply to landscape and amenity timing:

The Community Development Director shall have the ability to defer the installation of the landscaping and central amenities as noted below but may require performance securities and additional deposits to cover administrative costs. Under no circumstance shall landscaping be deferred if 80% of the units have been issued permits.

- a) Any landscape or open space lot shall be completed with the occupancy of any adjacent residential lot/unit.
- b) Prior to building permit issuance of 50% of the residential units within the tract, the Park, paseos and the Project or HOA amenities shall be constructed and open to the residents in the development.

## PRIOR TO FINAL INSPECTION

44. **Processing Fees.** Prior to issuance of building permits, the Planning Division shall determine if any fees for the project are in a negative balance. If so, any outstanding fees shall be paid by the applicant.
45. **Development Fees.** The applicant shall pay the following:
  - Development Impact Fees prior to issuance of building occupancy of each residential unit.
  - Quimby Fees prior to the issuance of building occupancy of each residential unit.
46. **Paleontological Monitoring Report.** Prior to issuance of a certificate of occupancy, the applicant shall submit to the Planning Division, an electronic copy of the Paleontology Monitoring Report. The report shall be certified by a professional paleontologist listed on Riverside County's Paleontology Consultant List. A deposit for the review of the report will be required.
47. **Anti-Graffiti Coating.** An anti-graffiti coating shall be provided on all block walls constructed as part of any phase of the Project, and written verification from the developer shall be provided to the Planning Division.
48. **Final Planning Inspection.** The applicant shall obtain final occupancy sign-off from the Planning Division for each building permit issued by scheduling a final Planning inspection prior to the final sign-off from the Building Department. Planning staff shall verify that all pertinent conditions of approval have been met, including compliance with the approved elevations, site plan, parking lot layout, decorative paving, public plazas, etc. The applicant shall have all required paving, parking, walls, site lighting, landscaping and automatic irrigation installed and in good condition.
49. **Soil Management Plan.** The applicant shall submit a Soil Management Plan (Report) to the Planning Division before the Landscape Installation Inspection. The report can be sent in electronically. Information on the contents of the report can be found in the County of Riverside Guide to California Friendly Landscaping page 16, #7, "What is required in a Soil Management Plan?"
50. **Landscape Inspections.** The applicant shall obtain a final certificate of completion from the Planning Division's Landscape Inspector for each building permit issued by scheduling a final landscape inspection prior to the final occupancy from the Planning Division.

**Section II:**  
**Building and Safety Department**  
**Conditions of Approval**

## **GENERAL CONDITIONS**

54. **Final Building & Safety Conditions.** Final Building & Safety Conditions will be addressed when building construction plans are submitted to Building & Safety for review. These conditions will be based on occupancy, use, the California Building Code (CBC), and related codes which are enforced at the time of building plan submittal.
55. **Compliance with Code.** All Design components shall comply with applicable provisions of the 2022 edition of the California Building, Plumbing and Mechanical Codes; 2022 California Electrical Code; California Administrative Code, 2022 California Energy Codes, 2022 California Green Building Standards, California Title 24 Disabled Access Regulations, and City of Menifee Municipal Code. If a code cycle changes prior to submission of any plans or documents, the plans submitted shall be updated to the current State of California, Title 24, Code of Regulations, City of Menifee Ordinance, or any other state, federal, or city requirements.
56. **Photovoltaic System.** A photovoltaic (PV) system shall be installed on the newly constructed dwelling units per State of California Assembly Bill 178 (AB-178). The PV plans may be deferred. The proposed location of the PV system shall be shown on the first submittal of the dwelling construction plans for review. Any deferred PV system plans shall be submitted and approved prior to the rough electrical inspection of the ADU.
57. **County of Riverside Mount Palomar Ordinance.** Applicant shall submit, at the time of plan review, a complete exterior site lighting plan with a “photometric study” showing compliance with County of Riverside Mount Palomar Ordinance Number 655 for the regulation of light pollution. All streetlights and other outdoor lighting shall be shown on electrical plans submitted to the Building & Safety Department. Any outside lighting shall be hooded and aimed not to shine directly upon adjoining property or public rights-of-way. All exterior LED light fixtures shall be 3,000 kelvin and below.
58. **Street Name Addressing.** Applicant must obtain street name addressing for all proposed buildings by requesting street name addressing and submitting a site plan for commercial, residential/tract, or multi-family residential projects.
59. **Obtain Approvals Prior to Construction.** Applicant must obtain all building plans and permit approvals prior to commencement of any construction work.
60. **Obtaining Separate Approvals and Permits.** The recreation center, pools, and other associated structures and amenities for the recreation center shall be permitted separately. Temporary construction/sales trailers, temporary power poles/generators, trash enclosures, patio covers, light standards,

building and monument signage, and any block walls will require separate approvals and permits. All parks that are a part of the development shall be permitted separately.

61. **Private Sanitary Sewer and Domestic Water Plan Approvals.** (If Applicable) On-site private sanitary sewer and domestic water plans will require separate approvals and permits from Building and Safety. One (1) set of digital or six (6) sets of plans shall be submitted.
62. **Demolition.** (If applicable) Demolition permits require separate approvals and permits. AQMD notification and approval may be required.
63. **Hours of Construction.** Signage shall be prominently posted at the entrance of the project indicating the hours of construction, as allowed by the City of Menifee Municipal Ordinance 8.01.010, for any site within one-quarter mile of an occupied residence. The permitted hours of construction are Monday through Saturday 6:30am to 7:00pm. No work is permitted on Sundays and nationally recognized holidays unless approval is obtained from the City Building Official or City Engineer.

**Provide a tract production application and sequence worksheet with the following information:**

1. Identify the applicant, developer/builder, tract, phase, and lot number(s) on the City's application form.
2. On a sequence worksheet, identify the addresses, assessor's parcel numbers, lot numbers, plan types, elevations, habitable square foot area, garage square foot area, patio/deck square footage and chosen options.
3. Clearly identify all options creating additional square feet, or changes to total square foot area
4. Identification of residential lots based on percentages required by the Community Development Department.

**Submit one (1) set of digital plans including but not limited to: fully dimensioned Structural, Architectural, Plumbing, Mechanical and Electrical Plans, floor, and site plans and, geotechnical reports. All digital plans shall be a minimum equivalent of 24" x 36" size media.**

**Site Plans**

1. Vicinity Map.
2. Assessor's Parcel Number, Tract and Lot number; and Site Address.
3. Building data: Proposed building Sq. Ft., use/occupancy, Building Code data: The California Model Codes currently in effect are the 2022 California

Code of Regulations, Title 24 – Building, Electrical, Mechanical, Plumbing, Green Building Code, Fire, and California Energy Code.

### **Floor Plans**

1. North Arrow.
2. Street frontage, lot lines and lot dimensions.
3. Building location and setbacks to property lines and/or easements.

### **Floor Plans**

1. Each model or building type.
2. Universal Design components for single- family residential dwellings.

### **Elevations**

All model or building types. Provide North, South, East, and West side views of the building exterior, showing the structure's exterior features and elements e.g., exterior wall finish, wall veneers, fireplace chimney, roof pitch, roof vents, doors, windows, etc.

### **Plumbing/Mechanical**

1. Points of connection for water/sewer meter locations.
2. Material type and sizes for waste/vent, water, and gas supply systems.
3. HVAC equipment location; gas stub locations and BTU input for gas appliances.
4. County of Riverside Environmental Health Department Approved septic system design.

### **Electrical Plan**

1. Electrical main service size, location, and grounding method.
2. Electrical power and lighting plans, lighting fixture schedule.
3. Title 24 Energy Code electrical requirements including high efficacy fixture types, motion sensors, dimmer switching or photo controls.
4. In single-family residential buildings that include one or two dwellings, each dwelling unit shall be provided with dedicated raceways, designated branch circuits and isolation devices for energy storage systems as specified in California Energy Code Section 150.0(s). Additionally, the panelboards shall be provided with the minimum busbar rating as specified in California Energy Code Section 150.0(s).

Alternatively, an energy storage systems (ESS) shall be installed with minimal backup capacity and ESS supplied branch circuits as specified in California Energy Code Section 150.0(s).



## **Structural Plan/Foundation/Framing/Roof Plan and Details**

1. Structural design by a State of California registered engineer or licensed architect if the proposed structure does not comply with conventional light wood framing.
2. Foundation elements to include, footing & slab reinforcement; footing and slab details, including base preparation, sand layer(s), moisture barrier; anchor bolt size and spacing, hold down devices, etc.
3. Structural frame plan(s) and key referenced details for walls, floor levels and roof.
4. One (set) set of stamped/signed (digital signature accepted) Structural Calculations.

One (1) digital set of stamped/signed (digital signature accepted) Roof Truss Calculations (if applicable). The architect or engineer of record shall first review and stamp the truss layout sheet, indicating the design to be in general conformance with the building design, prior to submittal to the Building and Safety Department for review and approval.

## **Supplemental Information**

1. One (1) digital copy of current Geotechnical soils reports, dated within 1 year of plan submittal or, an older report with an update letter addressing current soils data from the same engineering firm.
2. Package D prescriptive method Energy Forms, or computerized ENV (Envelope), MECH (Mechanical) and Mandatory Measures energy calculation forms for new conditioned space; and all the required compliance forms are to be copied to the full-size plan sheets.
3. Include full plan size copies of the city department's Conditions of Approval to the plans.
4. One (1) digital copy of the approved signed precise grading plan.
5. Fees are based on the current City of Menifee Adopted Fee Schedule.
6. The contractor must sign the permit application and provide evidence of current CA State contractor's license. All contractor's/sub-contractors must show proof of State and City licenses and shall comply with Sec. 3800 of the Labor Code regarding Workers Compensation.
7. Applicant shall obtain all required clearances and/or approvals from the appropriate water district(s) and Riverside County Fire prior to issuance of any building permits.

## **Prior to Issuance of Building Permits**

64. Prior to the model home complex, sales office, and production permits, all maps shall be recorded with the City of Menifee. With Building Official and Community Development Director approval, the model home complex and sales office may be constructed prior to final map recordation, subject to a Prior to Final Map Recordation Agreement and Bond.
65. All associated Building Fees to be paid.
66. Each Department is **required** to sign the City of Menifee request for residential permit issuance form available on the City of Menifee website. The Building and Safety Department shall be the last to sign the form.

### **Inspections**

- All inspection requests shall be requested through the City of Menifee Accella Citizen Access (ACA) portal only.
- All work that has been requested to be inspected shall be ready for inspection prior to 8:00am.
- The approved plans and documents shall be on-site at the time of inspection.
- Access to the job site shall be provided on the day of inspection by 8:00am.
- Any construction changes from the approved plans shall be revised on the plans and submitted to the Building and Safety Department for review and approval prior to the inspection.
- Any special inspection or deputy reports required by code, or the approved plans shall be provided at the time of inspection for the specific portion of work required the special inspection or deputy report.

### **Prior to Final Inspection**

Each department that has conditions shall have completed and approved their final inspection prior to requesting the final inspection by the Building and Safety Department.

Each Department is **required** to sign the City of Menifee request for residential occupancy form available on the City of Menifee website. The Building and Safety Department shall be the last to sign the form.

**EXHIBIT “1”**  
**CONDITIONS OF APPROVAL**

**Planning Application No.: PLN23-0246 Tentative Map 38766**

**Section III-A:**  
**Engineering/Public Works**  
**Department**  
**Conditions of Approval**

The following are the Public Works / Engineering Department Conditions of Approval for this project which shall be satisfied at no cost to the City or any other Government Agency. All questions regarding the intent of the following conditions shall be referred to the Public Works Engineering Department, Land Development Section. The developer / property owner shall use the standards and design criteria stated in the following conditions and shall comply with all applicable City of Menifee standards and ordinances. Should a conflict arise between City of Menifee standards and design criteria, and any other standards and design criteria, those of the City of Menifee shall prevail.

Tentative Tract Map 38766 at Garbani and Evans is a 20.03-acre subdivision for Single Family Residences. The map subdivided into 67 residential lots in a single phase, therefore, all public improvements shall be constructed prior to any issuance of occupancies. If the developer chooses to phase the subdivision map, additional phasing of the public improvements will be considered, and the applicable conditions will be updated.

It is understood that the tentative tract map must correctly show acceptable centerline elevations, all existing easements, traveled ways, cross sections, and drainage courses with appropriate drainage flows. Any omission or unacceptability may require the map to be resubmitted for further consideration. If there is a conflict between what is shown on the tentative tract map and these conditions, these conditions will supersede what is shown on the tentative tract map and any attachments to the tentative tract map, including the site plan and other plans or exhibits. All questions regarding the true meaning of these conditions shall be referred to the Public Works / Engineering Department. **Engineering Design exceptions to City design standards and policies must be specifically requested in**

**writing and approved by City Engineer/PW Director. Any design exceptions shown on the tentative map and associated engineering documents that are not specifically requested shall be redesigned to meet city standards.**

67. Drainage Study – The following report was reviewed and approved by the City:

- a. *Preliminary Hydrology Analysis for Tentative Tract Map No. 38766*, prepared by Hunsaker & Associates Irvine, Inc., dated August 21, 2024

The project shall comply with all mitigation recommended by the approved drainage study, and in accordance with City Standards. The design of drainage facilities will need to be revised if it does not adhere to City Standards.

Two copies of a final drainage study (also referred to as Hydrology/Hydraulics Report) shall be submitted to the City for review and approval. The study shall analyze at a minimum the following: project site drainage flow; all future improvements drainage flow; Q10, Q100, pre- and post- condition flow rates; anticipated total drainage flow into existing storm drain; and existing storm drain capacity. A fee for review of the Drainage Study shall be paid to the City, the amount of which shall be determined by City at first submittal of report.

68. Project Specific Water Quality Management Plan (WQMP). The following report was reviewed and approved by the City:

- a. *Preliminary Water Quality Management Plan “Garbani” Tract 38766*, prepared by Hunsaker & Associates Irvine, Inc., dated December 14, 2023. Revision Date June 7, 2024

Prior to issuance of a grading permit, a FINAL project specific WQMP in substantial conformance with the approved PRELIMINARY WQMP, shall be reviewed and approved by the Public Works Engineering Department. Final construction plans shall incorporate all the structural BMPs identified in the approved FINAL WQMP. The final developed project shall implement all structural and non-structural BMPs specified in the approved FINAL WQMP. One copy of the approved FINAL WQMP on a CD-ROM in pdf format shall be submitted to the Public Works Engineering Department. The FINAL WQMP submittal shall include at the minimum the following reports/studies:

- a. Hydrology/hydraulics report
- b. Soils Report that includes soil infiltration capacity
- c. Limited Phase II Environmental Site Assessment Report, as may be required by an approved Phase I ESA Report

Final construction plans shall incorporate all the structural BMPs identified in the approved FINAL WQMP. The final developed project shall implement all structural and non-structural BMPs specified in the approved FINAL WQMP. One copy of the approved FINAL WQMP on a CD-ROM in pdf format shall be submitted to the Public Works Engineering Department.

69. Geotechnical Report – The following documentation was reviewed and approved by the City:

*Preliminary Geotechnical Evaluation for the Proposed Residential Development, Northwest Corner of Evans Road and Garbani Road, City of Menifee CA Project No. 22235-01.* Prepared by LGC Geotechnical, Inc., dated January 31, 2023.

Two copies of City-approved geotechnical/soils report, no more than three (3) years from date of application for grading permit, shall be provided to the City Public Works / Engineering Department with initial submittal of a grading plan. If there is no approved report and/or said report is past three (3) years from date of application, a new geotechnical/soils report and/or update letter, respectively, shall be prepared and submitted to City for review and approval. The geotechnical/soils, compaction and inspection reports will be reviewed in conformance with the latest edition of the Riverside County Technical Guidelines for Review of Geotechnical and Geologic Reports. A fee for review of the geotechnical/soils report and/or update letter shall be paid to the City, the amount of which shall be determined by the City at the first submittal of the report.

Geotechnical Report – A preliminary geotechnical/soils report was submitted to the City and reviewed by staff. The geotechnical/soil report was reviewed in conformance with the latest edition of the Riverside County Technical Guidelines for Review of Geotechnical and Geologic Reports. Prior to issuance of any grading permit, two copies of the City approved final geotechnical/soils report shall be submitted to the Public Works Engineering Department. The developer/property owner shall comply with the recommendations of the report, and City standards and specifications. All grading shall be done in conformance with the recommendations of the report, and under the general direction of a licensed geotechnical engineer.

70. Off-Site Dedications - Prior to the approval of any improvement plans and the commencement of any construction associated with the development, the Developer shall be responsible for obtaining all necessary dedications of rights-of-way for offsite infrastructure improvements, right-of-entry for offsite grading, and easements for ingress, egress, drainage, utilities and other legal requirements for impacts associated with the development of this project, as determined and directed by the City Engineer. If the Developer cannot acquire a property interest in property required for off-site improvements, Government Code § 66462.5 shall apply and the City retains the right to:

- a. The Developer shall enter into an agreement to complete the improvements pursuant to Government Code § 66462 at such time as the City acquires an interest in the land that will permit the improvement to be made.
- b. The Developer shall pay all costs associated with acquiring the offsite real property interests required in connection with the development.
- c. In the instance where the developer and the city has made all reasonable efforts to negotiate the acquiring of said land, the developer may request that the city enter into the process of eminent domain, which shall be done in accordance with all applicable laws and regulations and at the discretion of City Approval.

71. Frontage Road Dedication. The developer / property owner shall dedicate the necessary Evans Road (Secondary Roadway per City Circulation Element) and Garbani Road (Collector Roadway per City Circulation Element) right of way fronting the development on the final map or through another acceptable recordable instrument prior to issuance of any building permit.

72. Traffic Study Report – The following VMT and LOS Traffic Impact Analysis for the proposed Garbani and Evans Road Project was reviewed and approved by the City:

*Transportation Impact Analysis Garbani and Evans TTM 38766*, prepared by Michael Baker International, dated August 27, 2024.

The Public Works Department – Traffic Engineering Division has reviewed the addendum and has generally concurred with its findings. The developer/property owner shall be responsible for all improvements and mitigations, required or identified in the approved traffic study and according to these Conditions of Approval, such as but not limited to right-of-way frontage improvements, traffic signal construction or modification, and fair share fees. All required improvements and mitigation measures identified in the study shall be included in all improvement plans for review and approval by the Public Works Department.

73. Reconstruction or Resurfacing of Frontage Roads – Per City Subdivision ordinance, projects are required to improve frontage streets to the ultimate half-width, plus 12 feet, with pavement structural sections meeting current city standards. The Public Works Director / City Engineer may consider reconstruction or resurfacing of Frontage Roads paving fronting the development to meet existing conditions, provided the road is found to meet the minimum City standards for pavement conditions at the time of project construction.

74. Signing and Striping – A signing and striping plan for the required improved roadways is required for this project along the project frontage, onsite, and off-site transitions to existing striping. The applicant shall be responsible for any additional paving and/or striping removal caused by the striping plan. The Signing and Striping Plan shall be approved by the City Engineer in accordance with City ordinances, standards, and specifications, and with the latest edition of the CAMUTCD

- a. The proposed project shall insure that adequate striping and signing is in place to insure safe pedestrian access to and from the existing school site during pickup and dropoff times.

75. Construction of Street and Wet Utility Improvements – The developer / property owner shall design and construct the following improvements:

- In-Tract Improvements - Construct all street, storm, sewer, water, park, and wall improvements to public agency engineering standards. These internal roadways shall be privately maintained by the project's HOA or other approved private maintenance entity. This includes the following street improvements:

- a. Internal Roadways – The developer / property owner shall construct internal roads to be privately owned and maintained by the HOA or

other approved private maintenance entity, in line with a modified private roadway, reference standard 124, with the difference being utilizing a 56' total Right-of-Way, with 36' Curb to Curb.

- b. Entry Street – The developer / property owner shall construct entry Street A, a modified section utilizing, with 70' Right-of-Way, 50' Curb to Curb and 6' Raised Median.
- c. Internal Traffic Calming Measures – The developer / property owner shall construct internal traffic calming measures at the intersections specified in the tentative map. These measures shall be built in such away that permits adequate circulation that does not conflict with the provided pedestrian walkways, as determined and approved by the City Engineer.
- Project Frontage Improvements – The developer / property owner shall construct frontage roads to its ultimate half-width plus 12 feet per City Standards along its entire project frontage, except as detailed below and as determined by the City Engineer.
  - d. Garbani Road – The developer / property owner shall construct Garbani Road along the southern frontage of the project to its ultimate half-width plus 12', with appropriate transitions back to existing roadway. Garbani Road is classified as a Collector Roadway (City Standard 113) in the City of Menifee General Plan. The project shall dedicate the ultimate half width ROW (37' from Centerline) and the roadway with shall be improved to be 22' of pavement from Centerline to Curb.
  - e. Evans Road- The developer / property owner shall construct Evans Road to its Ultimate Half-Width per City standards within the project limits with appropriate transitions in line with MUTCD Guidelines back to existing roadway improvements. Evans Road is Classified as a secondary roadway per the city's circulation element (City Standard 111). The project shall dedicate the ultimate half width ROW (50' from Centerline) and improve 32' of pavement from Centerline to Curb.

The required improvements shall include the construction of appropriate pavement transitions from the new improvements to existing improvements beyond the project frontage. The design of the transitions shall be in accordance with the CA Highway Design Manual and MUTCD, finalized during review of final construction drawings, and approved by the Public Works Director / City Engineer.

- f. Intersection Geometrics – The developer / property owner shall construct roadway intersections along the project frontages with geometrics consistent with the general plan roadway sections, as approved by the Public works Director / City Engineer.

- g. Evans Road and Garbani Road – As an interim improvement, Garbani and Evans Road shall be constructed as a stop-controlled intersection with the following geometrics:
    - a. Eastbound: Shared through-left turn lane
    - b. Westbound: Dedicated through lane, Right Turn Lane
    - c. Southbound: Dedicated Left Turn Lane, Right Turn Lane
  - h. Evans Road and “A” Street - The project proposes a single entrance into the residential development along Evans Road. This intersection shall provide full access in and out of the site, with the following geometrics
    - a. Eastbound: Dedicated Left Turn Lane, Right Turn Lane
    - b. Northbound: Striped Median shall be utilized to allow for a left turn into the project site. Existing Striping for through traffic shall be retained.
      - i. As noted in the Traffic Study Queuing Analysis, there shall be a minimum storage length of 100’ on Evans Road for the northbound left turn pocket.
    - i. Garbani Road Access – Due to an existing school south of the project on Garbani Road and to avoid unsafe pedestrian access, Garbani Road shall be restricted to emergency access only.
- 76. Landscaping on Frontage - The parkway areas within the public right-of-way or landscape easements fronting the entire property, shall be landscaped and irrigated per City standards and guidelines. -These areas shall be maintained by the CFD or HOA or approved maintenance entity.
- 77. RCFC Improvements – As proposed as apart of this project, there a facilities that shall be constructed that ultimately are maintained by RCFC and connect to an existing RCFC. These proposed improvement reviews shall be coordinated and approved by both the City of Menifee and Riverside County Flood Control (RCFC).
- 78. Underground Storage – The project utilizes underground storage for the project specific WQMP treatment. Note, that the use of Corrugated Metal Pipe (CMP) is not an acceptable material for systems due to material failure, corrosion, and increased cost of maintenance or replacement as noted the City of Menifee Storm Water Material Standards Memo dated February 5, 2024. Unless otherwise designated by the Public Works Director or City Engineer, Reinforced Concrete Pipe (RCP Preferred), PVC, HOPE, and other polyethylene solutions are acceptable for underground stormwater storage.
- 79. Fair Share Contributions. The project shall provide the following fair share contributions prior to any certificates of occupancy.
  - b. Evans Road and Craig Avenue – The project shall contribute fair share costs equal to 10.1% for the construction and installation of a Traffic Signal at the ultimate location for this intersection.
  - c. Evans Road and Garbani Road – The project shall contribute fair share costs equal to 13.7% for the construction and installation of a Traffic Signal at the ultimate location for this intersection.



General Conditions:

80. All required public improvements must be constructed and accepted by the City prior to issuance of the first and any subsequent certificate of occupancy, unless approved by City Engineer/Public Works Director.
81. Engineering Design exceptions to City design standards and policies must be specifically requested in writing and approved by City Engineer/PW Director. Any design exceptions shown on the tentative map and associated engineering documents that are not specifically requested are not approved.
82. The developer is responsible to furnish & install one 2" and one 3" conduit for traffic signal interconnect and broadband purposes, per City of Menifee Standard Detail 1005, along all circulation element roads and intersections along the project frontage.
83. Subdivision Map Act – The developer / property owner shall comply with the State of California Subdivision Map Act and all other laws, ordinances, and regulations pertaining to the subdivision of land.
84. Mylars – All improvement plans and grading plans shall be drawn on twenty-four (24) inch by thirty-six (36) inch Mylar and signed by a licensed civil engineer and/or other registered/licensed professional as authorized by State law.
85. Guarantee for Required Improvements. Prior to grading permit issuance, construction permit issuance, and/or Final Map recordation, financial security or bonds shall be provided to guarantee the construction of all required improvements associated with each phase of construction, per the City's municipal code.
86. The Public Works Director may require the dedication and construction of necessary utilities, streets, or other improvements outside the area of any particular map phase if the improvements are needed for circulation, drainage, parking, and access or for the welfare and safety of the public.
87. Bond Replacement, Reduction, and Releases - All requests for bond replacements (such as in changes of property ownerships), reductions (such as in partial completion of improvements), releases (such as in completion of improvements), shall conform to City policies, standards, and applicable City ordinances. It shall be the responsibility of the developer / property owner to notify the City in time when any of these bond changes are necessary. The City shall review all changes in Bond Agreements and the accompanying bonds or security.
88. Existing and Proposed Easements - The final grading plan and improvement plans shall correctly show all existing easements, traveled ways, drainage courses, and encumbrances. Any omission or misrepresentation of these documents may require said plan to be resubmitted for further consideration.
89. Engineered Plans. All improvement plans, and grading plans shall be drawn on twenty-four (24) inches by thirty-six (36) inch Mylar and signed by a licensed civil engineer or other registered/licensed professional as required.

90. **Plan Check Submittals** – Appropriate plan check submittal forms shall be completed and submittal check list provided that includes required plan copies, necessary studies / reports, references, fees, deposits, etc. Prior to final approval of improvement plans by the Public Works / Engineering Department, the developer / property owner shall submit to the Public Works / Engineering Department CAD layers of all improvements to be maintained by the City (pavement, sidewalk, streetlights, etc.). A scanned image of all final approved grading and improvement plans on a Universal Serial Bus (USB) drive, also known as a “flash” drive or “thumb” drive, shall be submitted to the Public Works / Engineering Department, in one of the following formats: (a) Auto CAD DXF, (b) GIS shapefile (made up of ESRI extensions .shp, .shx and .dbf) or (c) Geodatabase (made up of ESRI extension .gdb). CAD files created with the latest version shall only be accepted if approved by the Public Works Director / City Engineer. GIS and ACAD files 2004 or later are required for all final maps upon approval.
91. **Final Map Submittal Process** – Appropriate final map plan check submittal forms shall be completed, and appropriate fees or deposits paid. Prior to approval of the final map by the City Council, the developer / property owner shall provide along with the final map mylars, electronic files of the final map, in one of the following formats: (a) Auto CAD DXF, (b) GIS shapefile (made up of ESRI extensions .shp, .shx and .dbf) and (c) Geodatabase (made up of ESRI extension .gdb). CAD files created with the latest version shall only be accepted if approved by the Public Works Director / City Engineer.
92. **Plan Approvals** – Improvement plans and grading plans shall be submitted with necessary supporting documentation and technical studies (hydrology, hydraulics, traffic impact analysis, geotechnical studies, etc.) to the Public Works / Engineering Department for review and approval. All submittals shall be signed and date stamped by the Engineer of Record. The plans must receive Public Works / Engineering Department approval prior to issuance of any construction permit, grading permit, or building permits as applicable and as determined by the Public Works Director / City Engineer. All submittals shall include a completed City Fee or Deposit Based Worksheet and the appropriate plan check. For improvements proposed to be owned and maintained by the Riverside County Flood Control and Water Conservation District, improvement plans must receive district approval prior to Building permit issuance or as determined by the District.
- All required improvement plans and grading plans must be approved by the Public Works Engineering Department prior to recordation of a final map for which the improvements are required, or prior to issuance of any construction and/or grading permit, whichever comes first and as determined by the PW Director. Supporting City approved studies including, but not limited to, hydrologic and hydraulic studies and traffic studies must be provided prior to approval of plans. All required CFD landscape plans must be approved prior to building permit issuance.
93. **As-Built Plans**. Upon completion of all required improvements, the developer/property owner shall cause the civil engineer of record to as-built all project plans, and submit project base line of work for all layers on a USB drive to the Public Works / Engineering Department, in one of the following formats: (a) Auto CAD DXF, (b) GIS shapefile (made up of ESRI extensions .shp, .shx and .dbf) or (c) Geodatabase (made up of ESRI extension .gdb). The timing for submitting the as-built plans shall be as determined by the Public Works Director / City Engineer.

94. **Construction Times of Operation.** The developer / property owner shall monitor, supervise, and control all construction and construction related activities to prevent them from causing a public nuisance including, but not limited to, strict adherence to the following:
- a. Construction activities shall comply with City of Menifee ordinances relating to construction noise. Any construction within the City limits located 1/4 of a mile from an occupied residence shall be permitted Monday through Saturday, except on nationally recognized holidays, 7:00 a.m. to 7:00 p.m. in accordance with Municipal Code Section 8.01.020. There shall be no construction permitted on Sunday or nationally recognized holidays unless prior approval is obtained from the City Building Official or City Engineer.
  - b. Removal of spoils, debris, or other construction materials deposited on any public street no later than the end of each working day.
  - c. The construction site shall accommodate the parking of all motor vehicles used by persons working at or providing deliveries to the site. Violation of any condition or restriction or prohibition set forth in these conditions shall subject the owner, applicant to remedies as set forth in the City Municipal Code. In addition, the Public Works Director / City Engineer or the Building Official may suspend all construction related activities for violation of any condition, restriction or prohibition set forth in these conditions until such a time it has been determined that all operations and activities are in conformance with these conditions.
  - d. A Pre-Construction meeting is mandatory with the City's Public Works Inspection team prior to permit issuance and the start of any construction activities for this site.
95. **Dry Utility Installations.** Electrical power, telephone, communication, traffic signal, street lighting, and cable television conduits and lines shall be placed underground in accordance with current City Ordinance, and as approved by the Public Works Director / City Engineer. This applies also to existing overhead lines which are 33.6 kilovolts or below along the project frontage and within the project boundaries. In cases where 33.6kV or below lines are collocated with high voltage lines (for example, 115kV), the low voltage lines shall be placed underground even when the high voltage lines are exempt from relocation or undergrounding in accordance with City standards and ordinances. Exemption from undergrounding low voltage lines shall only be by the Public Works Director / City Engineer or as directed by the City Council.
96. All grading activities shall conform to the latest adopted edition of the California Building Code, City Grading Ordinance, Chapter 8.26, applicable City design standards and specifications, City ordinances, policies, rules and regulations governing grading in the City.
97. **Regulations and Ordinance on Grading Within the City.** In addition to compliance with City Chapter 8.26, grading activities shall also conform to the latest edition of the California Building Code, City General Plan, other City Ordinances, City design standards and specifications and all other relevant laws, rules and regulations governing grading in the City of Menifee. Prior to commencing any grading, clearing, grubbing or any topsoil disturbances, the applicant shall obtain a grading permit from

the Public Works / Engineering Department. Grading activities that are exempt from a grading permit as outlined by the City ordinance may still require a grading permit by the Public Works Director / City Engineer when deemed necessary to prevent the potential for adverse impacts upon drainage, sensitive environmental features, or to protect property, health safety, and welfare.

98. **Dust Control.** All necessary measures to control dust shall be implemented by the developer during grading. Fugitive dust shall be controlled in accordance with Rule 403 of the California Air Quality Control Board.
99. **2:1 Maximum Slope.** Graded slopes shall be limited to a maximum steepness ratio of 2:1 (horizontal to vertical) unless otherwise approved by the Public Works / Engineering Department.
100. **Slope Setbacks.** Observe slope setbacks from buildings and property lines per the California Building Code and City ordinance on grading.
101. **Slope Landscaping and Irrigation.** All slopes greater than or equal to 3 feet in vertical height shall be irrigated and landscaped with grass or ground cover. All manufactured slopes shall be irrigated and landscaped with grass or approved ground cover and shall have some type of drainage swale at the toe of the slope to collect runoff. Slopes exceeding 15 feet in vertical height shall be irrigated and planted with shrubs and/or trees per City Grading Ordinance Chapter 8.26. Drip irrigation shall be used for all irrigated slopes.
102. **Slope Erosion Control Plan.** Erosion control and/or landscape plans are required for manufactured slopes greater than 3 feet in vertical height. The plans shall be prepared and signed by a licensed landscape architect and bonded per applicable City ordinances.
103. **Slope Stability Report.** A slope stability report shall be submitted to the Public Works / Engineering Department for all proposed cut and fill slopes steeper than 2:1 (horizontal:vertical) or over 20 feet in vertical height, unless addressed in a previously city approved report.
104. **Erosion Control Plans.** All grading plans shall require erosion control plans prior to approval. Temporary erosion control measures shall be implemented immediately following rough grading to prevent deposition of debris onto downstream properties or drainage facilities. Plans showing erosion control measures may be included as part of the grading plans or submitted as a separate set of plans for city review and approval. Graded but undeveloped land shall provide, in addition to erosion control planting, any drainage facilities deemed necessary to control or prevent erosion. Erosion and sediment control BMPs are required year-round in compliance with all applicable City of Menifee Standards and Ordinances and the National Pollutant Discharge Elimination System (NPDES) Municipal Separate Storm Sewer System (MS4) Permit from the California State Water Resources Control Board (SWRCB). Additional Erosion protection may be required during the rainy season.
105. **Water Quality Management Plan (WQMP).** All grading plans shall require an approved copy of the Water Quality Management Plan sheet per the approved WQMP, executed report. The developer / property owner shall comply with the requirements

of the WQMP report, the NPDES municipal permit in force, and City standards and specifications.

106. **Design Grade Criteria.** Onsite parking areas shall be designed in accordance with the current version of City of Menifee Standards and Specifications. Non-compliance may require a redesign of the project. Significant redesigns may require a revised Plot Plan.

**Design Grade Criteria:**

- a. On-Site Parking – Where onsite parking is designed, such as in common areas, parking stalls and driveways shall not have grade breaks exceeding 4%. A 50' minimum vertical curve shall be provided where grade breaks exceed 4%. Five percent grade is the maximum slope for any parking area. Where ADA requirement applies, ADA requirement shall prevail.
  - b. Down Drains - Concrete down drains that outlet onto parking lot areas are not allowed. Drainage that has been collected in concrete ditches or swales should be collected into the receiving underground drainage system or should outlet with acceptable velocity reducers into BMP devices.
  - c. Pavement - Permeable pavement requires the layers of filter material to be installed relatively flat. As such, the permeable pavement areas should have a maximum surface gradient of 2%, or approved by the PW Director/City Engineer.
107. **Drainage Grade.** Minimum drainage design grade shall be 1% except on Portland cement concrete surfaces where 0.35% shall be the minimum. The engineer of record must submit a variance request for design grades less than 1% with a justification for a lesser grade.
108. **Finish Grade.** Shall be sloped to provide proper drainage away from all exterior foundation walls in accordance with City of Menifee Standard Plan 300.
109. **Use of Maximum and Minimum Grade Criteria.** Actual field construction grades shall not exceed the minimum and maximum grades for ADA and approved project grading design, to allow for construction tolerances. Any improvement that is out of the minimum and maximum values will not be accepted by the City Inspector and will need to be removed and replaced at the developer's or owner's expense.
110. **Licensed Geotechnical Engineer.** A California licensed Geotechnical Engineer shall perform final determination of the foundation characteristics of soils within on-site development areas, and per the approved geotechnical report reviewed and approved by the City.
111. **Retaining Walls.** Sections, which propose retaining walls, will require separate permits. They shall be obtained prior to issuance of any other building permits – unless otherwise approved by the Building Official and/or the Public Works Director / City Engineer. The walls shall be designed by a licensed civil engineer and conform to City Standards. The plans shall include plan and profiles sheets.
112. **Trash Racks.** Trash Racks shall be installed at all inlet structures that collect runoff from open areas with potential for large, floatable debris.

113. **Drainage Runoff Emergency Escape.** An emergency escape path shall be provided for the stormwater runoff at all inlets for the proposed underground facilities in the event that the inlets become blocked in any way. To prevent flood damage to the proposed structures, all proposed structures in the vicinity of the inlets and along the emergency escape path shall be protected from flooding by either properly elevating the finished floor in relation to the inlets and flow path or by making sure the structures are set back from the inlets to provide adequate flow through area in the event the emergency escape of the stormwater runoff is necessary.
114. **Riverside County Flood Control and Water Conservation District (RCFCWCD) Encroachment Permit Required.** An Encroachment Permit is required for any work within District right of way or any connection to District facilities. The Encroachment Permit application shall be processed and approved concurrently with the improvement plans.
115. **RCFCWCD Submittal of Plans.** A copy of the project specific WQMP, improvement plans, grading plans, BMP improvement plans and any other necessary documentation along with supporting hydrologic and hydraulic calculations (drainage report) shall be submitted to the District as reference material for the review and approval of the final drainage report and storm drain plans that propose construction of storm drain facilities that will be owned and maintained by the District.
116. **Grading Permit for Clearing and Grubbing.** City ordinance on grading requires a grading permit prior to clearing, grubbing, or any topsoil disturbances related to construction grading activities.
117. **Compliance with NPDES General Construction Permit.** The developer/property owner shall comply with the National Pollutant Discharge Elimination System (NPDES) General Construction Permit (GCP) from the State Water Resource Control Board (SWRCB). This is in addition to the Municipal permit governing design, WQMPs, and permanent BMPs.
- Prior to approval of the grading plans or issuance of any grading permit, the developer/property owner shall obtain a GCP from the SWRCB. Proof of filing a Notice of Intent (NOI) and monitoring plan, shall be submitted to the City; and the WDID number issued by the SWRCB shall be reflected on all grading plans prior to approval of the plans. For additional information on how to obtain a GCP, contact the SWRCB.
118. **SWPPP.** Prior to approval of the grading plans, the developer/property owner shall prepare a Storm Water Pollution Prevention Plan (SWPPP) for the development. The developer/property owner shall be responsible for uploading the SWPPP into the State's SMARTS database system and shall ensure that the SWPPP is updated to constantly reflect the actual construction status of the site. A copy of the SWPPP shall be made available at the construction site at all times until construction is completed. The SWRCB considers a construction project complete once a Notice of Termination has been issued by SWRCB. The City will require submittal of NOTs for requests to fully release associated grading bonds.
119. **SWPPP for Inactive Sites.** The developer/property owner shall be responsible for ensuring that any graded area that is left inactive for a long period of time has

appropriate SWPPP BMPs in place and in good working conditions at all times until construction is completed and the Regional Board has issued a Notice of Termination (NOT) for the development.

120. **Import/Export.** In instances where a grading plan involves import or export, prior to obtaining a grading permit, the developer/property owner shall have obtained approval for the import/export location from the Public Works / Engineering Department. If an Environmental Assessment did not previously approve either location, a Grading Environmental Assessment shall be submitted to the Planning Director for review and comment and to the Public Works Director / City Engineer for approval. Additionally, if the movement of import/export occurs using City roads, review, and approval of the haul routes by the Public Works / Engineering Department will be required. Import or export materials shall conform to the requirements of Chapter 8.26.
121. **Offsite Grading Easements.** Prior to recordation of a final map phase, or the issuance of a grading permit within a phased map whichever occurs first, the developer/property owner shall obtain all required easements and/or permissions to perform offsite grading, from affected land owners. Notarized and recorded agreement or documents authorizing the offsite grading shall be submitted to the Public Works Engineering Department.
122. **Offsite Property and Right of Way.** The developer / property owner shall be responsible for acquiring any offsite real property interests that may be required in connection with the development project. Prior to recordation of a final map, or the issuance of a grading permit, whichever occurs first, the developer shall obtain all required ROW, easements and / or permissions to perform offsite grading, from all affected landowners.
123. **Increased Runoff Criteria.** The development of this site would increase peak flow rates on downstream properties. Mitigation shall be required to offset such impacts. An increased runoff basin should be shown on the exhibit and calculations supporting the size of the basin shall be submitted to the District and the City for review. The entire area of proposed development will be routed through a detention facility(s) to mitigate increased runoff. All basins must have positive drainage; dead storage basins shall not be acceptable.

A complete drainage study including, but not limited to, hydrologic and hydraulic calculations for the proposed detention basin shall be submitted to the City for review and approval. For design purposes, the proposed detention basin shall be sized using the 6-hour/100-year frequency storm event. Detention basin(s) and outlet(s) sizing will ensure that this storm event does not produce higher peak discharge in the "after" condition than in the "before" condition. For the 100-year event, an AMC II shall be used together with a constant loss rate.

Low Loss rates will be determined using the following:

- a. Undeveloped Condition --> LOW LOSS = 90%
- b. Developed Condition --> LOW LOSS = .9 - (.8x%IMPERVIOUS)
- c. Basin Site --> LOW LOSS = 10%

Where possible and feasible the onsite flows should be mitigated before combining with offsite flows to minimize the size of the detention facility required. If it is necessary to combine offsite and onsite flows into a detention facility two separate conditions should be evaluated for each duration/return period/before-after development combination studied; the first for the total tributary area (offsite plus onsite), and the second for the area to be developed alone (onsite). It must be clearly demonstrated that there is no increase in peak flow rates under either condition (total tributary area or onsite alone), for each of the return period/duration combinations required to be evaluated. A single plot showing the pre-developed, post-developed and routed hydrographs for each storm considered, shall be included with the submittal of the hydrology study.

No outlet pipe(s) will be less than 18" in diameter. Where necessary an orifice plate may be used to restrict outflow rates. Appropriate trash racks shall be provided for all outlets less than 48" in diameter.

The basin(s) and outlet structure(s) must be capable of passing the 100-year storm without damage to the facility. Mitigation basins should be designed for joint use and be incorporated into open space or park areas. Side slopes should be no steeper than 4: 1 and depths should be minimized where public access is uncontrolled.

Mitigation basins should be designed for joint use and may be incorporated into open space or park areas. Side slopes should be not steeper than 4: 1 and depths should be minimized where public access is uncontrolled.

A viable maintenance mechanism, acceptable to the City should be provided for any flood control facilities to be owned and maintained by the City. Any facilities proposed to be owned by the District, should be provided with a viable maintenance mechanism acceptable to the City and the District. For the City this would be the citywide CFD. Facilities to remain private shall be maintained by commercial property owners association or homeowners associations.

124. **Site Drainage.** Positive drainage of the site shall be provided, and water shall not be allowed to pond behind or flow over cut and fill slopes. Where water is collected and discharged in a common area, protection of the native soils shall be provided by planting erosion resistant vegetation, as the native soils are susceptible to erosion by running water. All cut and fill slopes shall have a maximum 2:1 (H:V) grade, 2 horizontal to 1 vertical.
125. **Alteration of Drainage Patterns.** Prior to grading permit issuance or approval of improvement plans, the final engineering plans submitted by the applicant shall address the following: The project drainage system shall be designed to accept and properly convey all on- and off-site drainage flowing on or through the site. The project drainage system design shall protect downstream properties from any damage caused by alteration of drainage patterns such as concentration or diversion of flow. Concentrated drainage on commercial lots shall be diverted through parkway drains under sidewalks.
126. **100 Year Storm.** The 100-year storm flow shall be contained within the street top of curb.



127. **100 Year Drainage Facilities.** All drainage facilities shall be designed to accommodate 100-year storm flows as approved by the City of Menifee Public Works / Engineering Department.
128. **100 Year Design Criteria.** In final engineering and prior to grading permit issuance, subsurface storage systems shall be designed with emergency overflow inlets to mitigate flows in excess of the 100-year storm event in a controlled manner to the satisfaction of the Public Works / Engineering Department.
129. **100 Year Sump Outlet.** Drainage facilities outletting sump conditions shall be designed to convey the tributary 100-year storm flows. Additional emergency escape shall also be provided.
130. **Coordinate Drainage Design.** Development of this property shall be coordinated with the development of adjacent properties to ensure that watercourses remain unobstructed, and stormwaters are not diverted from one watershed to another. This may require the construction of temporary drainage facilities or offsite construction and grading. A drainage easement shall be obtained from the affected property owners for the release of concentrated or diverted storm flows. A copy of the recorded drainage easement shall be submitted to the PW Engineering Department for review.
131. **Comingling of Flows.** Site restrictions may require the comingling of onsite and offsite flows. A treatment device approved by the City of Menifee Public Works Director shall be utilized to pretreat the flows before entering HOA facilities. The WQMP will need to show these catch basin inserts. This comingling of flows and the easement shall also be clarified in the CC&Rs for the project. If site restrains and existing conditions require said comingling, it will be the obligation of the HOA to accept this water and maintain the system, as well as performing maintenance on the associated filter inserts. The developer shall provide a storm drain and flowage easement, or other applicable document approved by the city of Menifee, providing the right of the city to drain onto the private property.
132. **Interceptor Drain Criteria/Guidelines.** The criteria for maintenance access of terrace/interceptor is as follows: flows between 1-5 cfs shall have a 5-foot wide access road, flows between 6-10 cfs shall be a minimum 6-foot rectangular channel. Terrace/interceptor drains are unacceptable for flows greater than 10 cfs. Flows greater than 10 cfs shall be brought to the street. These guidelines may be modified by the City Engineer/PW Director.
133. **BMP – Energy Dissipators.** Energy Dissipators, such as rip-rap, shall be installed at the outlet of a storm drain system that discharges runoff flows into a natural channel or an unmaintained facility. The dissipators shall be designed to minimize the amount of erosion downstream of the storm drain outlet.
134. **Trash Racks.** Trash Racks shall be installed at all inlet structures that collect runoff from open areas with potential for large, floatable debris.
135. **Perpetuate Drainage Patterns.** The property's street and lot grading shall be designed in a manner that perpetuates the existing natural drainage patterns with respect to tributary drainage areas, outlet points and outlet conditions. Otherwise, a drainage easement shall be obtained from the affected property owners for the release

of concentrated or diverted storm flows. A copy of the recorded drainage easement shall be submitted to the City for review and approval.

136. **Perpetual Drainage Patterns (Easements).** Grading shall be designed in a manner that perpetuates the existing natural drainage patterns and conditions with respect to tributary drainage areas and outlet points. Where these conditions are not preserved, necessary drainage easements shall be obtained from all affected property owners for the release onto their properties of concentrated or diverted storm flows. A copy of the recorded drainage easement shall be submitted to the PW Engineering Department for review.
137. **Protection of Downstream Properties.** The developer/property owner shall protect downstream properties from damages that can be caused by alteration of natural drainage patterns, i.e., concentration or diversion of flow. Protection shall be provided by constructing adequate drainage facilities including enlarging existing facilities and securing necessary drainage easements.
138. **Storm Drain Lines 36" and larger.** All proposed storm drain lines greater than 36" in diameter may be considered for ownership and maintenance by the Flood Control District. The applicant shall enter into a cooperative agreement with the Flood Control District regarding the terms of the design, construction and operation of facilities proposed for ownership by the Flood Control District.
139. **No Building Permit without Legal Lot.** Prior to issuance of any building permit, the developer / property owner shall ensure that the underlying parcels for such buildings are complying with City Ordinances, Codes, and the Subdivision Map Act.
140. **No Building Permit Prior to Subdivision Map Recordation.** Prior to issuance of any building permit, the developer / property owner shall record the Subdivision Map. Model Homes are exempt from this requirement.
141. **No Building Permit without Grading Permit.** Prior to issuance of any building permit for any new structure or appurtenance, the developer/property owner shall obtain a grading permit and/or approval to construct from the Public Works Engineering Department.
142. **Final Rough Grading Conditions.** Prior to issuance of each building permit, the developer/property owner shall cause the Civil Engineer of Record and Soils Engineer of Record for the approved grading plans, to submit signed and wet stamped rough grade certification and compaction test reports with 90% or better compaction. The certifications shall use City approved forms and shall be submitted to the Public Works Engineering Department for verification and acceptance.
143. **Conformance to Elevations/Geotechnical Compaction.** Rough grade elevations for all building pads and structure pads submitted for grading plan check approval shall be in substantial conformance with the elevations shown on approved grading plans. Compaction test certification shall be in compliance with the approved project geotechnical/soils report.
144. **Final Grade Certification.** The developer/property owner shall cause the Civil Engineer of Record for approved grading plans, to submit signed and wet stamped final

grade certification on City-approved form, for each building requesting a certificate of occupancy. The certification shall be submitted to the Public Works Engineering Department for verification and acceptance.

145. **Conform to Elevations.** Final grade elevations of all building or structure finish floors submitted for grading plan check approval shall be in substantial conformance with the elevations shown on the approved grading plans. Compaction test certification shall be in compliance with the approved project geotechnical/soils report.
146. **Plant & Irrigate Slopes.** All manufactured slopes shall be irrigated and landscaped with grass or approved ground cover and shall have some type of drainage swale at the toe of the slope to collect runoff. Slopes greater than or equal to 3' in vertical height shall have erosion control measures provided. Slopes that exceed 15' in vertical height are to be planted with additional shrubs and trees as approved by the Public Works / Engineering Department. Drip irrigation shall be provided for all irrigated slopes.
147. **Common Area Maintenance.** Any common areas identified on the tentative map shall be owned and maintained through a permanent master maintenance organization shall be established for the project, to assume maintenance responsibility for all common areas. The organization may be public (City CFD, or another agency) or private (e.g., property owners' association). Merger with an area-wide or regional organization shall satisfy this condition provided that such organization is legally and financially capable of assuming the responsibilities for maintenance. When necessary, property dedication or easement dedications shall be granted to the maintenance organization through map dedication, or separate recordable instrument, and shall be in a form acceptable to the city.
148. **Maintenance Exhibit.** Prior to final map recordation, the developer / property owner shall prepare an exhibit that shows all open space lots within the project development tract and the maintenance entity for each lot. The exhibit shall be reviewed and approved by the Community Development Department and the Public Works / Engineering Department.
149. **Conditions, Covenants and Restrictions (Private Common Areas).** In the event that the Community Facilities District will not maintain all common areas, the establishment of a property owner association (POA or HOA) shall be the mechanism to maintain such common areas.
150. **CC&R Content, Submittal Process and Timing.** The developer/property owner shall submit to the Public Works / Engineering Department for review and approval CC&R documents or approved equivalent consisting of the following:
  - a. One hard copy and an electronic version of the CC&R's. A completed application form to review the CC&Rs, available at the Public Works / Engineering front counter. There is a fee associated with the application and required backup documents to review. The declaration of CC&R's shall:
    - i. provide for the establishment of a property owner's association,
    - ii. provide for the ownership of the common area by the property owner's association,

- iii. contain provisions approved by the Public Works / Engineering Department, Community Development Department, and the City Attorney,
  - iv. Contain provisions with regards to the implementation of post development Water Quality Best Management Practices identified in the project's approved WQMP.
  - v. Contain provisions notifying initial occupants, or tenants of the project of their receipt of educational materials on good housekeeping practices which contribute to the protection of storm water quality. These educational materials shall be distributed by the property owners' association and/or the developer.
  - vi. Contain provisions for allowing the City a Right of Entry to maintain BMPs that are otherwise not maintained by responsible property owners. If a separate Right of Entry Agreement has been executed, this provision is not necessary to be in the CC&Rs.
- b. As part of the CC&R document submittal, exhibit(s) identifying the areas or improvements that will be maintained by the POA, the CFD or other entities shall be provided. The exhibit shall be reviewed and approved by the City.
  - c. Once approved, the developer / property owner shall provide a hard copy of the CC&R's wet-signed and notarized to the Public Works / Engineering Department. The Public Works / Engineering Department shall record the original declaration of CC&R's prior to..... the issuance of Certificate of Occupancy or building permit issuance.
  - d. A deposit to pay for the review of the CC&Rs pursuant to the City's current fee schedule at the time the above-referenced documents are submitted to the Public Works / Engineering Department.
151. **Street Design Standards.** Street improvements shall conform to all applicable City Design Standards and Specifications, the City General Plan, Ordinances, and all other relevant laws, rules and regulations governing street construction in the City.
152. **Concrete Work.** All concrete work including curbs, gutters, sidewalks, driveways, cross gutters, catch basins, manholes, vaults, etc. shall be constructed to meet a 28-day minimum concrete strength of 3,250 psi.
153. **Intersection Geometrics** – All final intersection geometrics may be modified in final engineering as approved by the Public Works Director / City Engineer.
154. **Intersection / 50-Foot Tangent** – All centerline intersections shall be at ninety (90) degrees, plus or minus five (5) degrees, with a minimum fifty (50) foot tangent, measured from flow line / curb face or as approved by the Public Works Director / City Engineer.
155. **Street Improvements** – Street improvements shall conform to all applicable City Design Standards and Specifications, the City General Plan, and all other relevant laws, rules and regulations governing street construction in the City.

156. **Soils and Pavement Report** - Street pavement structural designs shall comply with the recommendations in the City approved project soils and pavement investigation report, and must meet minimum City standards and specifications, as approved by the Public Works Director / City Engineer. R-Values shall be provided in said report and the Engineer of Record shall provide pavement calculations to the City.
157. **Driveways** - Final driveway geometrics may be modified in final engineering as approved by the Public Works Director / City Engineer. Driveways shall meet current standard radii on all existing and proposed commercial drive approaches used as access to the proposed development. The developer shall adhere to all City standards and regulations for access and ADA guidelines.
158. **Acceptance of Public Roadway Dedication and Improvements** – Easements and right-of way for public roadways shall be granted to the City through acceptable recordable instrument. Onsite easements and right-of way for public roadways shall be granted to the City of Menifee through the final map, or other acceptable recordable instrument. Any off-site rights-of-way required for access road(s) shall be accepted to vest title in the name of the public if not already accepted. Any shared access roads necessary for the adequate circulation of the proposed project, shall be dedicated for reciprocal access by acceptable recordable instrument prior to any permit issuance.
159. **ADA Compliance** – ADA path of travel shall be designed at the most convenient accesses and the shortest distance to the buildings in accordance with ADA design standards and to the satisfaction of the Public Works Director / City Engineer and the City Building Official.
160. **Paving or Paving Repairs** – The applicant shall be responsible for obtaining the paving inspections required by Ordinance 461 and City of Menifee standards and ordinances. Paving and/or paving repairs for utility street cuts shall be per City of Menifee Standards and Specifications and as approved by the Public Works Director / City Engineer.
161. **Street Light Plan** – Street lights requiring relocations, or any required new streetlights shall be designed in accordance with current City Standards for LS-3 type streetlights. Street light construction plans shall be prepared as separate plans or combined with the public street improvement plans as approved by the Public Works Director / City Engineer.
162. **Public Streetlights Service Points** – All proposed public streetlights shall be provided with necessary appurtenances and service points for power, separate from privately owned streetlights. The developer/property owner shall coordinate with the PW Department and with Southern California Edison the assignment of addresses to streetlight service points. Service points for proposed public streetlights shall become public and shall be located within public right of way or within duly dedicated public easements.
163. **CFD Maintenance** - The property owner shall file for annexation or inclusion into the Citywide Community Facilities Maintenance District, CFD for street sweeping services, street pavement maintenance, landscaping, street lighting, etc.

164. **Offsite Grading** – A notarized and recorded agreement, or City-approved documents authorizing the offsite grading shall be submitted to the Public Works / Engineering Department.
165. **Sight Distance Analysis** – Sight distance analysis shall be conducted at all project roadway entrances for conformance with City sight distance standards. The analysis shall be reviewed and approved by the Public Works Director / City Engineer, and shall be incorporated in the final the grading plans, street improvement plans, and landscape improvement plans.
166. **Street Name Sign** - The developer/property owner shall install street name sign(s) in accordance with applicable City Standards, or as directed by the PW Engineering Department.
167. **Driveway Geometrics**- Final driveway geometrics may be modified in Final Engineering as approved by the Public Works Director. Driveways shall meet current standard radii on all existing and proposed commercial drive approaches used as access to the proposed development. The developer shall adhere to all City standards and regulations for access and ADA guidelines.
168. **Construction Traffic Control Plan** - Prior to start of any project related construction, the developer/property owner shall submit to the Public Works Engineering Department for review and approval, a Construction Traffic Control Plan in compliance with all applicable City ordinances, standards and specifications, and the latest edition of the CAMUTCD. This traffic control plan shall address impacts from construction vehicular traffic, noise, and dust and shall propose measures to mitigate these effects. The traffic control plan shall include a Traffic Safety Plan for safe use of public roads right-of-way during construction.
169. **Cost participation through Payment of TUMF and DIF for Improvements**- The developer/property owner's TUMF and DIF payment obligations shall be considered as cost participation for Project's required offsite improvements only when the offsite improvements for which credits are claimed, are eligible TUMF and/or DIF facilities at time of TUMF and DIF payments. Determination for TUMF credits shall be at the discretion of the Western Riverside Council of Governments (WRCOG), the governing authority, which shall include entering a three party TUMF Credit Agreement with the developer, WRCOG and the City of Menifee.
170. **Improvement Bonds** – Prior to improvement plan approval and issuance of any construction permit for all required onsite and offsite public improvements, the developer/project owner shall enter into a bond agreement and post acceptable bonds or security, to guarantee the completion of all required improvements. The bonds shall be in accordance with all applicable City ordinances, resolutions, and municipal codes.
171. **Encroachment Permits** – The developer/property owner shall obtain all required encroachment permits and clearances prior to start of any work within City, State, or local agency right-of-way.
172. **Stormwater Management** - All City of Menifee requirements for NPDES and Water Quality Management Plans (WQMP) shall be met per City of Menifee Municipal Code Chapter 15.01 for Stormwater/Urban Runoff Management Program unless otherwise

approved by the Public Works Director/City Engineer. This project is required to submit a project specific WQMP prepared in accordance with the latest WQMP guidelines approved by the Regional Water Quality Control Board.

**173. Trash Enclosures Standards and Specifications** – Storm runoff resulting in direct contact with trash enclosure, or wastewater runoff from trash enclosure are prohibited from running off a site onto the City MS4 without proper treatment. Trash enclosures in new developments and redevelopment projects shall meet new storm water quality standards including:

- a. Provision of a solid impermeable roof with a minimum clearance height to allow the bin lid to completely open.
- b. Constructed of reinforced masonry without wooden gates. Walls shall be at least 6 feet high.
- c. Provision of concrete slab floor, graded to collect any spill within the enclosure.
- d. All trash bins in the trash enclosure shall be leak proof with lids that are continuously kept closed.
- e. The enclosure area shall be protected from receiving direct rainfall or run-on from collateral surfaces.
- f. The trash enclosure shall be lockable and locked when not in use with a 2-inch or larger brass resettable combination lock. Only employees and staff authorized by the enclosure property owner shall be given access.

Any standing liquids within the trash enclosures without floor drain must be cleaned up and disposed of properly using a mop and a bucket or a wet/dry vacuum machine. All non-hazardous liquids without solid trash may be put in the sanitary sewer as an option, in accordance with Eastern Municipal Water District (EMWD) criteria.

An alternate floor drain from the interior of the enclosure that discharges to the sanitary sewer may be constructed only after obtaining approval from EMWD. This option requires the following:

- a. The trash enclosure shall be lockable and locked when not in use with a 2-inch or larger brass resettable combination lock. Only employees and staff authorized by the enclosure property owner shall be given access. This requirement may not be applicable to commercial complexes with multiple tenants.
- b. A waterless trap primer shall be provided to prevent escape of gasses from the sewer line and save water.
- c. Hot and cold running water shall be provided with a connection nearby with an approved backflow preventer. The spigot shall be protected and located at the rear of the enclosure to prevent damage from bins.

**174. SWRCB, TRASH AMENDMENTS.** The State Water Resources Control Board (State Board) adopted amendments to the Water Quality Control Plan for Ocean Waters of California and the Water Quality Control Plan for Inland Surface Waters, Enclosed Bays, and Estuaries – collectively referred to as the “Trash Amendments.” Applicable requirements per these amendments shall be adhered to with implementation measures, prior to building permit issuance. Projects determined to be within Priority Land Uses as defined in the Trash Amendments, shall provide trash full capture devices in all new and existing catch basins to which this development will be tributary to or receiving from all Priority Land Use areas that will contribute storm water runoff to the City of Menifee’s

MS4. All trash full capture devices shall be listed on the State Board's current list of certified full capture devices posted on their website ([https://www.waterboards.ca.gov/water\\_issues/programs/stormwater/trash\\_implementation.shtml](https://www.waterboards.ca.gov/water_issues/programs/stormwater/trash_implementation.shtml)), or otherwise approved by State or Regional Water Quality Control Board staff. Storm water runoff from privately owned Priority Land Use areas shall be treated by full capture devices located within privately owned storm drain structures or otherwise located on the privately owned property, whenever possible. Runoff from Priority Land Use areas created or modified by the project, and which are proposed to be City owned, shall be treated by full capture devices located within city-owned storm drains or otherwise located within the public right of way.

175. Prior to issuance of a grading permit, a FINAL project specific WQMP in substantial conformance with the approved PRELIMINARY WQMP, shall be reviewed and approved by the Public Works Engineering Department. Final construction plans shall incorporate all the structural BMPs identified in the approved FINAL WQMP. The final developed project shall implement all structural and non-structural BMPs specified in the approved FINAL WQMP. One copy of the approved FINAL WQMP on a CD-ROM in pdf format shall be submitted to the Public Works Engineering Department. The FINAL WQMP submittal shall include at the minimum the following reports/studies:

- a. Hydrology/hydraulics report
- b. Soils Report that includes soil infiltration capacity
- c. Limited Phase II Environmental Site Assessment Report, as may be required by an approved Phase I ESA Report

Final construction plans shall incorporate all the structural BMPs identified in the approved FINAL WQMP. The final developed project shall implement all structural and non-structural BMPs specified in the approved FINAL WQMP. One copy of the approved FINAL WQMP on a CD-ROM in pdf format shall be submitted to the Public Works Engineering Department.

176. **Revising The Final WQMP** - In the event the Final WQMP requires design revisions that will substantially deviate from the approved Prelim WQMP, a revised or new WQMP shall be submitted for review and approval by the Public Works / Engineering Department. The cost of reviewing the revised/new WQMP shall be charged on a time and material basis. The fixed fee to review a Final WQMP shall not apply, and a deposit shall be collected from the applicant to pay for reviewing the substantially revised WQMP.

177. **WQMP Maintenance Agreement** - All water quality features or BMPs shall be located within the property limits, and the maintenance shall be the full responsibility of the developer / project owner. Prior to, or concurrent with the approval of the FINAL WQMP, the developer / property owner shall record Covenants, Conditions and Restrictions (CC&R's) that addresses the implementation and maintenance of proposed WQMP BMPs, or enter into an acceptable maintenance agreement with the City to inform future property owners of the requirement to perpetually implement the approved FINAL WQMP.

178. **Implement Project Specific WQMP** - All structural BMPs described in the project-specific WQMP shall be constructed or installed and operational in conformance with



approved plans and specifications. It shall be demonstrated that the applicant is prepared to implement all BMPs described in the approved project specific WQMP and that copies of the approved project-specific WQMP are available for the future owners/occupants. The City will not release occupancy permits for any portion of the project or subdivision map phase until all proposed BMPs described in the approved project specific WQMPs, to which the portion of the project is tributary to, are completed and operational.

The City will not release occupancy permits for any portion of the project, or any proposed map phase prior to the completion of the construction of all required structural BMPs, and implementation of non-structural BMPs.

179. **Inspection of BMP Installation** – Prior to issuance of Certificate of Occupancy, all structural BMPs included in the approved FINAL WQMP shall be inspected for completion of installation in accordance with approved plans and specifications, and the FINAL WQMP. The Public Works Stormwater Inspection team shall verify that all proposed structural BMPs are in working conditions, and that a hard copy and / or digital copy of the approved FINAL WQMP are available at the site for use and reference by future owners/occupants. The inspection shall ensure that the FINAL WQMP at the site includes the **BMP Operation and Maintenance Plan**, and shall include the site in a City maintained database for future periodic inspection.

180. **WQMP/BMP Education** - Prior to issuance of Certificate of Occupancy, the developer / project owner shall provide the City proof of notification to future occupants of all BMP's and educational and training requirements for said BMP's as directed in the approved WQMP. Proof of notification shall be provided to the Public Works / Engineering Department in forms determined acceptable by the Public Works Director / City Engineer. Public Education Program materials may be obtained from the Riverside County Flood Control and Water Conservation District's NPDES Section through their website at [www.rcwatershed.org](http://www.rcwatershed.org). The developer must provide to the Public Works / Engineering Department a notarized affidavit, or other notification forms acceptable to the Public Works Director / City Engineer, stating that the distribution of educational materials to future homebuyers has been completed prior to issuance of occupancy permits.

A copy of the notarized affidavit must be placed in the final WQMP report. The Public Works / Engineering Department MUST also receive the original notarized affidavit with the plan check submittal to clear the appropriate condition. Placing a copy of the affidavit without submitting the original will not guarantee clearance of the condition.

181. **EMWD Minimum Standards** – All public water, sewer and recycled water improvements shall be designed per the City adopted Ordinances; Eastern Municipal Water Districts (EMWD) standards and specifications, including required auxiliaries and appurtenances. The final design, including pipe sizes and alignments, shall be subject to the approval of EMWD and the City of Menifee.

182. **Utility Improvement Plans** – Public Water, Sewer and Recycled Water improvements shall be drawn on City title block for review and approval by the Public Works / Engineering Department and EMWD.

183. **Onsite and Offsite Sewer, Water and Recycled Water Improvements** – All public onsite and offsite sewer, water and recycled water improvements shall be guaranteed for construction prior to approval of improvement plans and final map approval.
184. **Sewer Lines** – Any new public sewer line alignments or realignments shall be designed such that the manholes are aligned with the center of lanes or on the lane line and in accordance with Riverside County Ordinances 460/461 and Eastern Municipal Water District standards.
185. **Water Mains and Hydrants** - All water mains and fire hydrants providing required fire flows shall be constructed in accordance with the Riverside County Ordinance Numbers 460 and 787, and subject to the approval of the Eastern Municipal Water District and the Riverside County Fire Department.
186. **Annexation to the Citywide Community Facilities District (CFD)** - Prior to map recordation, the developer/property owner shall complete the annexation of the proposed development, into the boundaries of the City of Menifee citywide Community Facilities Maintenance District (Services) CFD. The citywide CFD shall be responsible for:
- The maintenance of public improvements or facilities that benefit this development, including but not limited to, public landscaping, streetlights, traffic signals, streets, pavement maintenance, drainage facilities, street sweeping, water quality basins, graffiti abatement, and other public improvements or facilities as approved by the Public Works Director.
- The developer/property owner shall be responsible for all cost associated with the annexation of the proposed development in the citywide CFD.
187. **CFD Annexation Agreement** - In the event timing for this development's schedule prevents the developer/property owner from complying with condition of approval for CFD annexation, the developer shall enter into a CFD annexation agreement to allow the annexation to complete after map recordation but prior to issuance of a building permit issuance. The developer shall be responsible for all costs associated with the preparation of the CFD annexation agreement. The agreement shall be approved by the City Council prior to map recordation.
188. **Assessment Segregation** - Should this project lie within any assessment/benefit district, the applicant shall, prior to any building permit issuance to make application for and pay for their reapportionment of the assessments or pay the unit fees in the benefit district unless said fees are deferred to building permit.
189. **Landscape Improvement Plans for CFD Maintenance** – Landscape improvements within public ROW and/or areas dedicated to the City for the citywide CFD to maintain shall be prepared on a separate City CFD plans for review and approval by the PW Engineering Department. The plans may be prepared as one plan for the entire development as determined by the PW Director. When necessary, as determined by the PW Director, a separate WQMP construction plan on City title block may be required for review and approval by the PW Engineering Department prior to issuance of a grading permit.

190. **Parkway Landscaping Design Standards** - The parkway areas behind the street curb within the public's right-of-way, shall be landscaped and irrigated per City standards and guidelines.
191. **CFD Landscape Guidelines and Improvement Plans** – All landscape improvements for maintenance by the CFD shall be designed and installed in accordance with City CFD Landscape Guidelines, and shall be drawn on a separate improvement plan on City title block. The landscape improvement plans shall be reviewed and approved by the PW Engineering Department prior to issuance of a construction permit.
192. **Maintenance of CFD Accepted Facilities** – All landscaping and appurtenant facilities to be maintained by the citywide CFD shall be built to City standards. The developer shall be responsible for ensuring that landscaping areas to be maintained by the CFD have its own controller and meter system, separate from any private controller/meter system.
193. **AB 341.** AB 341 focuses on increased commercial waste recycling as a method to reduce greenhouse gas (GHG) emissions. The regulation requires businesses and organizations that generate four or more cubic yards of waste per week and multifamily units of 5 or more, to recycle. A business shall take at least one of the following actions to reuse, recycle, compost, or otherwise divert commercial solid waste from disposal:
- a. Source separate recyclable and/or compostable material from solid waste and donate or self-haul the material to recycling facilities.
  - b. Subscribe to a recycling service with their waste hauler.
  - c. Provide recycling service to their tenants (if commercial or multi-family complex).
  - d. Demonstrate compliance with the requirements of California Code of Regulations Title 14.

For more information please visit:

[www.rivcowm.org/opencms/recycling/recycling\\_and\\_compost\\_business.html#mandatory](http://www.rivcowm.org/opencms/recycling/recycling_and_compost_business.html#mandatory)

194. **AB 1826.** AB 1826 (effective April 1, 2016) requires businesses that generate eight (8) cubic yards or more of organic waste per week to arrange for organic waste recycling services. The threshold amount of organic waste generated requiring compliance by businesses is reduced in subsequent years. Businesses subject to AB 1826 shall take at least one of the following actions in order to divert organic waste from disposal:

Source separate organic material from all other recyclables and donate or self-haul to a permitted organic waste processing facility.

Enter into a contract or work agreement with gardening or landscaping service provider or refuse hauler to ensure the waste generated from those services meet the requirements of AB 1826.

Consider xeriscaping and using drought tolerant/low maintenance vegetation in all landscaped areas of the project.

As of January 1, 2019, the above requirements are now applicable to businesses that generate four (4) or more cubic yards of solid waste per week and one (1) or more cubic yards of organic waste per week. Additionally, as of January 1, 2019, a third trash bin is now required for organics recycling, which will require a larger trash enclosure to accommodate three (3) trash bins. This development is subject to this requirement.

195. **Recyclables Collection and Loading Area Plot Plan.** Prior to the issuance of a building permit for each building, the applicant shall submit three (3) copies of a Recyclables Collection and Loading Area plot plan to the City of Menifee Engineering/Public Works Department for review and approval. The plot plan shall show the location of and access to the collection area for recyclable materials, along with its dimensions and construction detail, including elevation/façade, construction materials and signage. The plot plan shall clearly indicate how the trash and recycling enclosures shall be accessed by the hauler.

The applicant shall provide documentation to the Community Development Department to verify that Engineering and Public Works has approved the plan prior to issuance of a building permit.

196. **Waste Recycling Plan.** Prior to the issuance of a building permit for each building, a Waste Recycling Plan (WRP) shall be submitted to the City of Menifee Engineering/Public Works Department for approval. Completion of Form B "Waste Reporting Form" of the Construction and Demolition Waste Diversion Program may be sufficient proof of WRP compliance, as determined by the Public Works Director / City Engineer. At minimum, the WRP must identify the materials (i.e., concrete, asphalt, wood, etc.) that will be generated by construction and development, the projected amounts, the measures/methods that will be taken to recycle, reuse, and/or reduce the amounts of materials, the facilities and/or haulers that will be utilized, and the targeted recycling or reduction rate. During project construction, the project site shall have, at a minimum, two (2) bins; one for waste disposal and the other for recycling of Construction and Demolition (C&D) materials. Additional bins are encouraged to be used to further source separation of C&D recyclable materials. Accurate record keeping (receipts) for recycling of C&D recyclable materials and solid waste disposal must be kept. Arrangements can be made through the franchise hauler.

197. **Waste Management Clearance.** Prior to issuance of an occupancy permit for each building, evidence (i.e., receipts or other type of verification) shall be submitted to demonstrate project compliance with the approved WRP to the Engineering and Public Works Department in order to clear the project for occupancy permits. Receipts must clearly identify the amount of waste disposed and Construction and Demolition (C&D) materials recycled. Completion of Form C, "Waste Reporting Form" of the Construction and Demolition Waste Diversion Program along with the receipts may be sufficient proof of WRP compliance, as determined by the PW Director / City Engineer.

198. **Fees and Deposits –** Prior to approval of final maps, grading plans, improvement plans, issuance of building permits, and/or issuance of certificate of occupancy, the developer/property owner shall pay all fees, deposits as applicable. These shall include the regional Transportation Uniform Mitigation Fee (TUMF), any applicable Traffic Signal Mitigation Fees, Development Impact Fees (DIF), and any applicable Road and Bridge Benefit District (RBBBD) Fee. Said fees and deposits shall be collected at the

rate in effect at the time of collection as specified in current City resolutions and ordinances, to the extent permitted by SB 330.

199. **Road Bridge Benefit District Scott Road Zone B** –The applicant shall pay the RBBD fees based on the designated land use and areas, prior to the issuance of a building permit. Should the project proponent choose to defer the time of payment, a written request shall be submitted to the City, deferring said payment from the time of issuance of a building permit to issuance of a certificate of occupancy. Fees which are deferred shall be based upon the fee schedule in effect at the time of issuance of the permit of each parcel.
200. **TUMF FEES** - Prior to the issuance of an occupancy permit, the developer/property owner shall pay the Transportation Uniform Mitigation Fee (TUMF) in accordance with the fee schedule in effect at the time of (building permit or certificate of occupancy) issuance, pursuant to adopted City Ordinance governing the TUMF program.
201. **Fees and Deposits** – Prior to approval of final maps, grading plans, improvement plans, issuance of building permits, and/or issuance of certificate of occupancy, the developer/property owner shall pay all fees, deposits as applicable. These shall include the regional Transportation Uniform Mitigation Fee (TUMF), any applicable Traffic Signal Mitigation Fees, Development Impact Fees (DIF), and any applicable Road and Bridge Benefit District (RBBD) Fee. Said fees and deposits shall be collected at the rate in effect at the time of collection as specified in current City resolutions and ordinances, to the extent permitted by SB 330.

**Section IV:**  
**Riverside County Fire Department**  
**Conditions of Approval**

202. **Roadways.** Roadways less than 30 feet parking prohibited. Roadway is required to be posted as a FIRE LANE.
203. **Surface load and capabilities.** Fire apparatus access roads shall be designed to support the impose loads of fire apparatus [80,000 pound live load (gross vehicular weight) distributed over two axles] and shall be surfaced so as to provide all-weather driving capabilities [rear wheel drive apparatus] for the length and grade(s) of the fire apparatus access road.
204. **Fire department access.** Fire apparatus access roads shall extend to within 150 feet of all portions of the facility and all portions of the exterior walls of the first story of the building as measured by an approved route around the exterior of the building or facility.
205. **Turning radius.** The minimum required turning radius of a fire apparatus access road is 38 feet outside radius and 14 feet inside radius.
206. **Single family dwellings.** Standard fire hydrants (6" x 4" x 2 1/2") shall be spaced no more than 500 feet apart in any direction so that no point on the street is more than 250 feet from a hydrant. Where new water mains are extended along streets where hydrants are not needed for protection of structures, standard fire hydrants shall be provided at spacing not to exceed 1000 feet along streets for transportation hazards. (CFC 507.3, Appendix B).
207. **Residential fire sprinkler.** Residential fire sprinklers are required in all one- and two-family dwellings per the California Residential code, California Building Code and the California Fire Code. Install Fire Sprinkler Systems per NFPA 13D, 2023 Edition. Plans must be submitted to the Fire Dept. for review and approval prior to installation.
208. **Potential fire flow.** The water system shall be capable of providing a fire flow of 1,500 GPM for 2 hours duration at a minimum of 20 PSI operating pressure from each fire hydrant.
209. **Address.** Multi-family residences shall display the address in accordance with the Riverside County Fire Department Premises Identification standard 07-01. (CFC 505.1)
210. **Water plans.** The applicant or developer shall furnish one copy of the water system plans to the Fire Department for review. Plans shall be signed by a registered civil engineer, containing a Fire Department approval signature block, and shall conform to hydrant type, location, spacing and minimum fire flow. Once plans are signed by local water company, the originals shall be presented to the Fire Department for signature. (PRIOR TO MAP RECORDATION)
211. **Gates.** Gate entrances shall be at least two feet wider than the width of the traffic lanes serving the gate. Any gate providing access from a road to a

driveway shall be located at least 35 feet setback from the roadway and shall open to allow a vehicle to stop without obstructing traffic on the road. Where a one-way road with a single traffic lane provides access to a gate entrance, a 38 feet turning radius shall be used. (PRIOR TO MAP RECORADATION)

212. **Auto gates.** Gates shall be automatic minimum 24 feet in width. Gate access shall be equipped with a rapid entry system to include OPTICOM and Knox Electric switches. Plan shall be submitted to the Fire Department for approval prior to installation. Automatic/manual gate pins shall be rated with shear pin force, not to exceed 30 pounds. Automatic gates shall be equipped with emergency backup power. Gates activated by the rapid entry system shall remain open until closed by the rapid entry system. (PRIOR TO MAP RECORDATION)
213. **Approved AM&M.** An approved fire apparatus access road was permitted to be restricted to emergency response personnel when approved by RVC -OFM and Public Works Department. Approved 8/27/24 (PRIOR TO MAP RECORDATION)
214. **ECS-WTR prior to combustibles.** The following note to be added to the ECS map: The required water system, including fire hydrants, shall be installed and accepted by the appropriate water agency prior to any combustible building material placed on an individual lot.
215. **Tract water verification.** The required water system, including all fire hydrant(s), shall be installed and accepted by the appropriate water agency and the Riverside County Fire Department prior to any combustible building material placed on an individual lot. Contact the Riverside County Fire Department to inspect the required fire flow, street signs, all weather surface, and all access and/or secondary. Approved water plans must be at the job site. - (PRIOR TO BUILDING PERMIT)
216. **Hydrant system.** Prior to the release of your installation, site prep and/or building permits from Building and Safety. Written certification from the appropriate water district that the required fire hydrant(s) are either existing or that financial arrangements have been made to provide them. Also, a map or APN page showing the location of the fire hydrant and access to the property. (PRIOR TO BUILDING PERMIT)
217. **Blue dot reflectors.** Blue retro-reflective pavement markers shall be mounted on private streets, public streets and driveways to indicate location of fire hydrants. Prior to installation, placement of markers must be approved by the Riverside County Fire Department.
218. **Secondary access.** In the interest of Public Safety, the project shall provide an Alternate or Secondary Access(s). Said Alternate or Secondary Access(s) shall



have concurrence and approval of both the Engineering Department and the Riverside County Fire Department.

219. **Grades.** Unless otherwise approved, the grade of a fire apparatus access road shall not exceed 16 percent and the cross slope shall not exceed 2.5 percent. The angles of approach and departure for fire apparatus access roads shall be a maximum of 6 percent grade change for 25 feet of approach/departure.

**The undersigned warrants that he/she is an authorized representative of the project referenced above, that I am specifically authorized to consent to all of the foregoing conditions, and that I so consent as of the date set out below.**

---

Signed

---

Date

---

Name (please print)

---

Title (please print)